

SUMMARY OF QUANTITIES			URBAN	100% STATE		SUMMARY OF QUANTITIES			URBAN	100% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	BRIDGE 0014	CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	BRIDGE 0014
20200100	EARTH EXCAVATION	CU YD	190	190		44201341	CLASS C PATCHES, TYPE II, 9 INCH	SO YD	32	32	
21101815	COMPOST FURNISH AND PLACE, 4"	SO YD	637	637		44201345	CLASS C PATCHES, TYPE III, 9 INCH	SO YD	40	40	
25000310	SEEDING, CLASS 4	ACRE	0.2	0.2		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	516	516	
25100630	EROSION CONTROL BLANKET	SO YD	637	637		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20		50300225	CONCRETE STRUCTURES	CU YD	28.5		28.5
28000305	TEMPORARY DITCH CHECKS	FOOT	108	108		50300255	CONCRETE SUPERSTRUCTURE	CU YD	155.1		155.1
28000400	PERIMETER EROSION BARRIER	FOOT	630	630		50300260	BRIDGE DECK GROOVING	SO YD	565		565
28000510	INLET FILTERS	EACH	2	2		50300300	PROTECTIVE COAT	SO YD	680		680
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SO FT	2355		2355
40600300	AGGREGATE (PRIME COAT)	TON	4	4		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	44900		44900
40600400	MIXTURE FOR CRACK, JOINTS AND FLANGEWAYS	TON	2	2		50901750	PARAPET RAILING	FOOT	22		22
40600625	LEVELING BINDER (MACHINE METHOD) N50	TON	64	64		51500100	NAME PLATES	EACH	1		1
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SO YD	42	42		52000110	PREFORMED JOINT STRIP SEAL	FOOT	47		47
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	11	11		59000200	EPOXY CRACK INJECTION	FOOT	147		147
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	79	79		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	289	289		60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1	
44000100	PAVEMENT REMOVAL	SO YD	94	94		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	597	597	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	597	597		63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	54	54	
44002207	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 3/4"	SO YD	106	106	*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SO YD	24	24	*	63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	4	4	

* SPECIALTY ITEMS

LONCO, INC.
CONSULTING ENGINEERS
1560 HALL ST, SUITE 222
HAVERVILLE, ILLINOIS 60562 PH: 630/577-9100

DESIGNED - ST
DRAWN - ST
CHECKED - MJY, SLV
DATE - 03/29/2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
PARK AVENUE OVER CALUMET UNION DRAINAGE DITCH

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 98+20 TO STA. 101+60

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3597	0710 B	COOK	30	3
D-91-292-09		CONTRACT NO. 60F95		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		