CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION TYPE CODES: ROADWAY IL 38/KAUTZ, KANE COUNTY, 80% FED 20% STATE, 0004	ROADWAY IL 38/KAUTZ, DUPAGE COUNTY, 80% FED 20% STATE, 0004	BRIDGE SN 045-0079 (PROPOSED), KANE COUNTY, 80% FED 20% STATE, 0008	SAFETY TRAFFIC SIGNALS, KANE COUNTY, 80% FED 13.2% STATE 3.4% GENEVA 3.4% WEST CHICAGO, 0021	SAFETY LIGHTING, KANE COUNTY, 100% STATE, 0021	WATER MAIN & CASING, KANE COUNTY, 100% GENEVA, 0043	CASING PIPE, DUPAGE COUNTY, 100% WEST CHICAGO, 0043	WATER MAIN & SANITARY, KANE COUNTY, 80% FED. 20% STATE, 0043	BIKE PATH, DUPAGE COUNTY, 80% FED. 20% DUPAGE CTY, 0028
51203200	TEST PILE METAL SHELLS	EACH	6			6						
51500100	NAME PLATES	EACH	1			1						
52000110	PREFORMED JOINT STRIP SEAL	FOOT	514			514						
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	31			31						
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	13			13						
52100540	ANCHOR BOLTS, 1 1/2"	EACH	120			120						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	11	3	8							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	14	14								
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2		2							
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2								
54215418	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"	EACH	1	1								
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	2	2								
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2		2							
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	2		2							
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	2	2								
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	121	66	55							
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	90	49	41							
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	343	186	157							
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	22	12	10							
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	97	53	44							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	757	409	348							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3,207	1,732	1,475							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	433	234	199							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	957	517	440							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	2,982	1,611	1,371							
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	541	293	248							
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1,324	715	609							
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	200	108	92							
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	167	91	76							
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	337	182	155							
550A0980	STORM SEWERS, CLASS A, TYPE 4 18"	FOOT	215	117	98							
550A1620	STORM SEWERS, CLASS A, TYPE 6 36"	FOOT	673	364	309							
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	335	181	154							
550B0020	STORM SEWERS, CLASS B, TYPE 1 6"	FOOT	235						88	147		
55100500	STORM SEWER REMOVAL 12"	FOOT	1,620	875	745							

• DENOTES SPECIALTY ITEM

△ DENOTES 100% FUNDING BY WEST CHICAGO FIRE PROTECTION DISTRICT

McDonough Associates Inc.
Engineers / Architects
130 East Randolph Street Chicago, Illinois 60601

FILE NAME = D160122-SHT-S0003.dgn	USER NAME = EricG	DESIGNED - MJT	REVISED -
		DRAWN - MJT	REVISED -
	PLOT SCALE = 1:50	CHECKED - EJG	REVISED -
	PLOT DATE = 11/9/2011	DATE - 10/14/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 3 OF 9 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	LY (HB & VB)	DUPAGE/KANE	421	6
	SQ-3	CONTRACT NO. 60122		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		