

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES								
				ROADWAY IL 38/KAUTZ		BRIDGE SN 045-0079 (PROPOSED)	SAFETY TRAFFIC SIGNALS	SAFETY LIGHTING	WATER MAIN & CASING	CASING PIPE	WATER MAIN & SANITARY	BIKE PATH
				KANE COUNTY	DUPAGE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	KANE COUNTY	DUPAGE COUNTY	KANE COUNTY	DUPAGE COUNTY
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 13.2% STATE 3.4% GENEVA 3.4% WEST CHICAGO	100% STATE	100% GENEVA	100% WEST CHICAGO	80% FED 20% STATE	80% FED 20% DUPAGE CTY
0004	0004	0008	0021	0021	0043	0043	0043	002B				
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1				1					
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8				8					
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4				4					
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	28				28					
87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	1				1					
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5				5					
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1				1					
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1				1					
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5				5					
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2				2					
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1				1					
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10				10					
88700200	LIGHT DETECTOR	EACH	3				3					
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1				1					
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4				4					
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,502				1,502					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1					
89502380	REMOVE EXISTING HANDHOLE	EACH	16				16					
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	11				11					
A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	14	8	6							
A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	11	6	5							
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	13	8	5							
A2006616	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	6	4							
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	15	9	6							
K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	32.40	18.00	14.40							
K0013060	PERENNIAL PLANTS, SEDGE MEADOW TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	0.64	0.35	0.29							
K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	50	27	23							
X0320374	PLUG EXISTING SANITARY SEWERS	EACH	3								3	
X0322464	ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	7								7	
X0322791	FILL EXISTING SANITARY SEWERS	CU YD	80								80	
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	18	10	8							
X0324097	COARSE SAND PLACEMENT, 2"	SO YD	94,940	51,268	43,672							
X0324534	REMOVE AND REINSTALL LIGHT POLES	L SUM	1						1			
X0325323	MANHOLES, TYPE A, SANITARY, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9								9	
X0326020	UTILITY PROTECTION PAD	SO YD	16		16							

• DENOTES SPECIALTY ITEM  
 Δ DENOTES 100% FUNDING BY WEST CHICAGO FIRE PROTECTION DISTRICT

FILE NAME = D160122-SHT-50087.dgn	USER NAME = EricG	DESIGNED - MJT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. = 347	SECTION = LY (HB & VB)	COUNTY = DUPAGE/KANE	TOTAL SHEETS = 421	SHEET NO. = 10
PLOT SCALE = 1:50	CHECKED - EJG	REVISED -	SCALE: NONE SHEET NO. 7 OF 9 SHEETS STA. TO STA.			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 12/14/2011	DATE = 12/09/11	REVISED -	CONTRACT NO. 60122							
						SQ-7				