

EARTHWORK SCHEDULE	STAGE 1						STAGE 2						STAGE 3					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
4046+00.00 TO 4047+00.00	342.50	291.13	217.80	73.33	313.59	74.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4047+00.00 TO 4048+00.00	477.98	406.28	174.37	231.91	346.31	86.67	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4048+00.00 TO 4049+00.00	750.28	637.74	201.02	436.72	393.98	113.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4049+00.00 TO 4050+00.00	589.17	500.79	186.74	314.05	338.70	99.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4050+00.00 TO 4051+00.00	215.78	183.41	169.33	14.08	197.96	46.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4051+00.00 TO 4052+00.00	192.43	163.56	299.96	-136.40	190.20	43.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4052+00.00 TO 4052+61.46	138.09	117.38	291.07	-173.69	168.17	44.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

EARTHWORK SCHEDULE	STAGE 1						STAGE 2						STAGE 3					
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
MAINLINE I-94 (NORTHBOUND)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
4052+61.49 TO 4053+00.00	40.36	34.30	113.59	-79.29	72.13	19.95	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4053+00.00 TO 4054+00.00	81.35	69.15	193.48	-124.33	151.44	39.70	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4054+00.00 TO 4055+00.00	75.15	63.88	85.80	-21.92	94.15	21.43	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4055+00.00 TO 4055+79.30	53.01	45.06	109.74	-64.68	92.75	24.82	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4055+79.30 TO 4056+00.00	10.86	9.23	36.83	-27.60	31.88	9.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4056+00.00 TO 4056+50.01	20.92	17.78	36.09	-18.31	41.91	11.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4058+47.74 TO 4059+00.00	32.89	27.96	1,257.81	-1,229.85	216.44	68.97	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4059+00.00 TO 4060+00.00	56.37	47.91	1,869.13	-1,821.21	406.93	128.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4060+00.00 TO 4061+00.00	57.93	49.24	1,200.07	-1,150.84	389.17	119.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4061+00.00 TO 4062+00.00	55.72	47.36	935.37	-888.01	388.63	119.48	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4062+00.00 TO 4063+00.00	51.76	44.00	1,007.04	-963.04	410.00	128.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4063+00.00 TO 4063+09.98	5.12	4.35	112.96	-108.62	41.77	13.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4063+09.98 TO 4063+50.82	20.13	17.11	482.11	-465.00	173.96	55.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4067+60.87 TO 4068+00.00	15.41	13.10	46.03	-32.93	71.08	21.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4068+00.00 TO 4069+02.05	47.53	40.40	30.20	10.20	66.09	16.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4069+02.05 TO 4070+00.00	39.83	33.86	61.35	-27.49	49.85	8.63	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4070+00.00 TO 4071+00.00	30.93	26.29	100.13	-73.84	76.78	12.94	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4071+00.00 TO 4072+00.00	32.81	27.89	786.56	-758.66	175.70	41.81	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4072+00.00 TO 4073+00.00	40.67	34.57	1,366.80	-1,332.23	272.26	68.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4073+00.00 TO 4074+00.00	52.65	44.75	1,193.52	-1,148.77	262.19	61.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4074+00.00 TO 4074+18.37	9.48	8.06	206.14	-198.08	47.37	10.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4074+18.37 TO 4075+00.00	100.18	85.15	493.36	-408.21	134.46	28.57	98.45	83.69	8.36	75.33	15.15	5.05	46.09	39.18	0.00	39.18	0.00	0.00
4075+00.00 TO 4075+18.37	22.92	19.48	179.87	-160.39	36.17	8.07	23.97	20.38	2.82	17.56	6.24	2.08	10.56	8.97	0.00	8.97	0.00	0.00
4075+18.37 TO 4076+00.00	70.82	60.20	1,258.33	-1,198.13	257.62	59.59	140.66	119.56	21.04	98.52	35.80	9.77	45.05	38.29	0.00	38.29	0.00	0.00
4076+00.00 TO 4077+00.00	163.11	138.64	1,134.70	-996.06	271.22	69.67	152.56	129.67	23.89	105.78	36.98	11.96	44.93	38.19	0.00	38.19	0.00	0.00
4077+00.00 TO 4078+00.00	226.56	192.57	1,100.22	-907.65	275.96	70.07	121.89	103.61	24.83	78.77	34.39	11.96	32.41	27.55	0.00	27.55	0.00	0.00
4078+00.00 TO 4079+00.00	228.24	194.00	1,142.85	-948.85	322.81	72.67	116.37	98.91	22.50	76.41	27.17	7.06	30.78	26.16	0.00	26.16	0.00	0.00
4079+00.00 TO 4080+00.00	188.17	159.94	1,149.06	-989.11	332.63	76.46	119.44	101.53	17.83	83.69	19.83	2.07	28.20	23.97	0.00	23.97	0.00	0.00
4080+00.00 TO 4081+00.00	85.61	72.77	1,218.24	-1,145.47	318.78	69.04	113.63	96.59	18.57	78.01	25.46	2.44	24.63	20.94	0.00	20.94	0.00	0.00
4081+00.00 TO 4082+00.00	18.63	15.84	1,114.98	-1,099.15	297.93	63.83	126.33	107.38	24.02	83.36	38.04	4.72	27.31	23.22	0.00	23.22	0.00	0.00
4082+00.00 TO 4083+00.00	22.13	18.81	786.69	-767.88	248.61	54.22	141.61	120.37	17.46	102.91	35.61	3.28	31.20	26.52	0.00	26.52	0.00	0.00
4083+00.00 TO 4084+00.00	18.85	16.02	514.65	-498.62	185.28	36.06	122.13	103.81	34.85	68.96	43.56	6.22	28.87	24.54	0.00	24.54	0.00	0.00
4084+00.00 TO 4085+00.00	39.59	33.65	295.37	-261.72	142.59	26.54	113.93	96.84	50.15	46.69	53.04	9.69	30.11	25.59	0.00	25.59	0.00	0.00
4085+00.00 TO 4086+00.00	134.31	114.17	98.72	15.45	74.04	12.69	133.69	113.63	30.80	82.84	40.26	5.24	35.07	29.81	0.00	29.81	0.00	0.00
4086+00.00 TO 4087+00.00	157.19	133.61	23.76	109.85	50.83	2.22	91.04	77.38	27.70	49.68	40.31	4.83	40.96	34.82	0.00	34.82	0.00	0.00
4087+00.00 TO 4088+00.00	63.65	54.10	115.30	-61.20	110.15	13.61	85.69	72.83	34.61	38.22	46.57	7.02	39.59	33.65	0.00	33.65	0.00	0.00
4088+00.00 TO 4089+00.00	51.61	43.87	293.13	-249.26	149.20	25.80	82.50	70.13	26.52	43.61	41.37	5.11	39.04	33.18	0.00	33.18	0.00	0.00
4089+00.00 TO 4090+00.00	44.50	37.83	455.70	-417.88	173.69	32.48	75.65	64.30	250.07	-185.77	88.83	19.61	36.06	30.65	0.00	30.65	0.00	0.00
4090+00.00 TO 4091+00.00	40.17	34.14	754.50	-720.36	225.74	47.96	66.19	56.26	316.09	-259.84	128.30	31.19	31.15	26.48	0.00	26.48	0.00	0.00
4091+00.00 TO 4092+00.00	37.39	31.78	945.76	-913.98	249.33	54.50	64.91	55.17	123.28	-68.11	99.22	21.06	28.33	24.08	0.00	24.08	0.00	0.00
4092+00.00 TO 4093+00.00	42.70	36.30	834.72	-798.42	238.85	49.17	68.76	58.45	86.91	-28.46	81.28	14.70	31.15	26.48	0.00	26.48	0.00	0.00
4093+00.00 TO 4094+00.00	45.22	38.44	690.24	-651.80	219.85	41.15	60.17	51.14	72.56	-21.41	75.67	11.33	31.67	26.92	0.00	26.92	0.00	0.00
4094+00.00 TO 4095+00.00	36.35	30.90	387.59	-356.69	205.8													