



- NOTES:**
1. THE REMOVAL OF EXISTING UNDERPASS LUMINAIRES MUST INCLUDE THE REMOVAL OF ALL CABLES, CONDUIT, JUNCTION BOXES, AND HARDWARE ASSOCIATED WITH THE EXISTING UNDERPASS LIGHTING. THE COST OF THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED AS PART OF THE "REMOVAL OF LIGHTING UNIT, SALVAGE" PAY ITEM.
 2. THE EXISTING UNDERPASS LIGHTING SHALL NOT BE REMOVED UNTIL THE PROPOSED UNDERPASS LIGHTING SYSTEM HAS BEEN ACTIVATED.



SCALE: 1" = 20'

E-13A

s:\projects\2012 us 41-usa to il 173 - bba\project work\disciplines\electrical\sheet\13a-light-13a.dgn

EJM ENGINEERING, INC.
 411 South Wells Street Suite 1000
 Chicago, Illinois 60607

FILE NAME	USER NAME = rsonson	DESIGNED - RAS	REVISED -
		DRAWN - BHH	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED - MKR	REVISED -
	PLOT DATE = 6/18/2012	DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**NB I-94 AT SB US 41
 UNDERPASS LIGHTING REMOVAL PLAN**

SCALE: 1"=20' SHEET NO. 13A OF 53 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	373A
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	