

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	110,964	110,964									
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	73,153	73,153									
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	5,134	5,134									
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	614	614									
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,225	1,923					2,302				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (3")	TON	69	69									
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	18,966	18,966									
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	6,058	6,058									
42000541	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SO YD	66,949	43,607					23,342				
42001300	PROTECTIVE COAT	SO YD	20,017	20,017									
44000100	PAVEMENT REMOVAL	SO YD	69,793	65,508					4,285				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	519	519									
44000300	CURB REMOVAL	FOOT	954	292					662				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	691						691				

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



* SPECIALTY ITEMS

FILE NAME : #FILES#	USER NAME : default	DESIGNED - JMC	REVISED -
		DRAWN - JMC	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 3 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	6
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

S:\181\05_CAD\60L77_IL_173168.77_Sheets\60L77-INT.dwg