

SUMMARY OF QUANTITIES

| CODE NO   | ITEM   | UNIT  | TOTAL QUANTITY | CONSTRUCTION CODE      |                         |             |                                 |              |                         |             |                  |  |  |
|-----------|--|-------|----------------|------------------------|-------------------------|-------------|---------------------------------|--------------|-------------------------|-------------|------------------|--|--|
|           |  |       |                | 90% FEDERAL, 10% STATE |                         |             |                                 | 100% ISTHA   |                         |             | 100% LOCAL NTFPD |  |  |
|           |  |       |                | 0003 ROADWAY           | 0010 BRIDGE SN 049-0535 | 0021 SAFETY | 0040 RETAINING WALL SN 049-W045 | 0003 ROADWAY | 0010 BRIDGE SN 049-0535 | 0021 SAFETY | 0021 SAFETY      |  |  |
|           |  |       |                |                        |                         |             |                                 |              |                         |             |                  |  |  |
| 60600095  | CLASS SI CONCRETE (OUTLET)                         | CU YD | 3              | 3                      |                         |             |                                 |              |                         |             |                  |  |  |
| 60600605  | CONCRETE CURB, TYPE B                              | FOOT  | 66             | 66                     |                         |             |                                 |              |                         |             |                  |  |  |
| 60602800  | CONCRETE GUTTER, TYPE B                            | FOOT  | 320            | 320                    |                         |             |                                 |              |                         |             |                  |  |  |
| 60603800  | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12  | FOOT  | 130            | 130                    |                         |             |                                 |              |                         |             |                  |  |  |
| 60605000  | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24  | FOOT  | 2,507          | 2,507                  |                         |             |                                 |              |                         |             |                  |  |  |
| 60617310  | PAVED DITCH, TYPE B-22                             | FOOT  | 125            | 125                    |                         |             |                                 |              |                         |             |                  |  |  |
| 60618320  | CONCRETE MEDIAN SURFACE, 6 INCH                    | SO FT | 5,412          | 5,412                  |                         |             |                                 |              |                         |             |                  |  |  |
| 60624600  | CORRUGATED MEDIAN                                  | SO FT | 2,348          | 2,348                  |                         |             |                                 |              |                         |             |                  |  |  |
| *63000001 | STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS   | FOOT  | 3,075          |                        |                         |             | 3,075                           |              |                         |             |                  |  |  |
| *63100045 | TRAFFIC BARRIER TERMINAL, TYPE 2                   | EACH  | 8              |                        |                         |             | 4                               |              |                         |             | 4                |  |  |
| *63100070 | TRAFFIC BARRIER TERMINAL, TYPE 5                   | EACH  | 1              |                        |                         |             | 1                               |              |                         |             |                  |  |  |
| *63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6                   | EACH  | 3              |                        |                         |             | 3                               |              |                         |             |                  |  |  |
| *63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH  | 13             |                        |                         |             | 5                               |              |                         |             | 8                |  |  |
| 63200310  | GUARDRAIL REMOVAL                                  | FOOT  | 10,609         |                        |                         |             | 6,912                           |              |                         |             | 3,697            |  |  |

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com



\* SPECIALTY ITEMS

|                     |                     |                  |           |   |                              |                          |         |            |                    |                     |                |                     |                 |
|---------------------|---------------------|------------------|-----------|---|------------------------------|--------------------------|---------|------------|--------------------|---------------------|----------------|---------------------|-----------------|
| FILE NAME - 4FILES4 | USER NAME - default | DESIGNED - JMG   | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> |                          |         |            | F.A. RTE.<br>94    | SECTION<br>49-1-R-1 | COUNTY<br>LAKE | TOTAL SHEETS<br>677 | SHEET NO.<br>12 |
|                     |                     | DRAWN - JMG      | REVISED - |   | SCALE: NA                    | SHEET NO. 9 OF 29 SHEETS | STA. NA | TO STA. NA | CONTRACT NO. 60L77 |                     |                |                     |                 |
|                     |                     | CHECKED - RGR    | REVISED - |   | ILLINOIS FED. AID PROJECT    |                          |         |            |                    |                     |                |                     |                 |
|                     |                     | DATE - 6/19/2012 | REVISED - |   |                              |                          |         |            |                    |                     |                |                     |                 |

9:11:05 AM C:\PDS\94L77-1L\13168L77\Sheets\186L77-12.rvt