

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120			IL ROUTE 137		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
			ROADWAY NEW CON. 0001	ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	376	193	18	0	165	0	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	552	364	0	0	188	0	0
20101000	TEMPORARY FENCE	FOOT	2,005	655	1,350	0	0	0	0
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7	0	5	0	2	0	0
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	6	0	3	0	3	0	0
20200100	EARTH EXCAVATION	CU YD	26,891	22,128	1,046	0	3,717	0	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	22,411	20,415	0	0	1,996	0	0
20400800	FURNISHED EXCAVATION	CU YD	14,100	14,100	0	0	0	0	0
20800150	TRENCH BACKFILL	CU YD	355	262	90	0	3	0	0
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	12,914	10,669	634	0	1,611	0	0
25000200	SEEDING, CLASS 2	ACRE	6.94	6.94	0	0	0	0	0
25000210	SEEDING, CLASS 2A	ACRE	4.11	2.11	0	0	2.00	0	0
25000300	SEEDING, CLASS 3	ACRE	2.06	2.06	0	0	0	0	0
25000350	SEEDING, CLASS 7	ACRE	16.02	13.23	0.79	0	2.00	0	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,443	1,191	72	0	180	0	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,443	1,191	72	0	180	0	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,443	1,191	72	0	180	0	0
25100115	MULCH, METHOD 2	ACRE	8.09	7.30	0.79	0	0	0	0
25100630	EROSION CONTROL BLANKET	SQ YD	35,806	26,139	0	0	9,667	0	0
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	834	834	0	0	0	0	0
25200110	SODDING, SALT TOLERANT	SQ YD	6,726	2,923	3,803	0	0	0	0
25200200	SUPPLEMENTAL WATERING	UNIT	105	64	35	0	6	0	0
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	492	444	0	0	48	0	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,602	1,323	79	0	200	0	0
28000400	PERIMETER EROSION BARRIER	FOOT	5,297	2,528	382	0	2,387	0	0
28000500	INLET AND PIPE PROTECTION	EACH	46	32	14	0	0	0	0
28100101	STONE RIPRAP, CLASS A1	SQ YD	112	112	0	0	0	0	0
28100105	STONE RIPRAP, CLASS A3	SQ YD	478	478	0	0	0	0	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	169	169	0	0	0	0	0
28100109	STONE RIPRAP, CLASS A5	SQ YD	121	121	0	0	0	0	0
28200200	FILTER FABRIC	SQ YD	1,021	1,021	0	0	0	0	0
30300112	AGGREGATE SURGRADE IMPROVEMENT 12"	SQ YD	22,724	17,032	1,758	0	3,934	0	0
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1,882	400	757	0	725	0	0
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	606	472	122	0	12	0	0
35501314	HOT MIX ASPHALT BASE COURSE, 1 1/2"	SQ YD	881	0	881	0	0	0	0

\* = SPECIALTY ITEM



DESIGNED - JSM  
DRAWN - JSM  
CHECKED - JMK  
DATE - 02/06/12

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: 1/2"=1' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. 198	SECTION 00-00045-00-PV	COUNTY LAKE	TOTAL SHEETS 195	SHEET NO. 4
CONTRACT NO. 63640				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				