


SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120			IL ROUTE 137		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
			ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	555	417	123	0	15	0	0
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	3,498	0	0	0	3,498	0	0
35501325	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	386	0	386	0	0	0	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16,072	10,869	1,842	0	3,361	0	0
40600300	AGGREGATE (PRIME COAT)	TON	39	7	14	0	18	0	0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	736	0	425	0	311	0	0
40600895	CONSTRUCTING TEST STRIP	EACH	2	0	1	0	1	0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BLITT JOINT	SQ YD	88	0	61	0	27	0	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	167	55	110	0	2	0	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	565	0	565	0	0	0	0
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	914	0	0	0	914	0	0
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	14,775	14,775	0	0	0	0	0
42001300	PROTECTIVE COAT	SQ YD	1,913	1,380	425	0	108	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	329	0	0	329	0	0	0
42400800	DETECTABLE WARNINGS	SQ FT	94	0	0	94	0	0	0
44000100	PAVEMENT REMOVAL	SQ YD	2,531	1,473	704	0	354	0	0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,460	0	5,460	0	0	0	0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,731	70	0	0	4,661	0	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	735	428	198	0	109	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	444	373	23	0	48	0	0
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	94	0	50	0	44	0	0
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	143	0	99	0	44	0	0
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	143	0	99	0	44	0	0
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	423	0	334	0	89	0	0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,098	0	0	378	0	720	0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	122	0	0	0	0	122	0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,103	0	0	378	0	725	0
50105220	PIPE CULVERT REMOVAL	FOOT	341	147	125	0	69	0	0
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	14	0	0	0	14	0	0
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	32	32	0	0	0	0	0
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	80	80	0	0	0	0	0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	3	1	0	0	0	0
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	1	0	0	1	0	0
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	0	0	0	0	0

* = SPECIALTY ITEM

	DESIGNED: JSM DRAWN: JSM CHECKED: DNM DATE: 02/06/12	REVISED: - REVISED: REVISED: REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.J. RTE. 198 SECTION 00-00345-00-PV COUNTY LAKE TOTAL SHEETS 5 SHEETS NO. 5 CONTRACT NO. 63640
	SCALE: 1/8"=1'-0" SHEET NO. 05 OF SHEETS 10 STA. 10+00.00 TO STA. 10+00.00	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			