

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				HPP FUNDS					
				ATKINSON ROAD & IL ROUTE 120		IL ROUTE 137		-	
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
		ROADWAY NEW CON. 0001	ROADWAY RECON. 0004	SAFETY 0021	ROADWAY RECON. 0004	SAFETY 0021	TRAINEES 0042		
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	0	0	1	0	0	0
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	861	0	0	91	0	770	0
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	95	0	0	95	0	0	0
* 81028330	UNDERGROUND CONDUIT, PVC, 1 1/4" DIA.	FOOT	95	0	0	95	0	0	0
* 81400100	HANDHOLE	EACH	1	0	0	0	0	1	0
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4	0	0	0	0	4	0
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	321	0	0	321	0	0	0
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	428	0	0	428	0	0	0
* 83500200	LIGHT POLE FOUNDATION, 24" DIAMETER	EACH	2	0	0	2	0	0	0
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	2	0	0	2	0	0	0
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2	0	0	2	0	0	0
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	0	0	0	0	2	0
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	0	0	1	0	0	0
* X811215	RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1	0	0	0	0	1	0
* X800105	MASTER CONTROLLER (SPECIAL)	EACH	1	0	0	0	0	1	0
* 87200400	SPAN WIRE	FOOT	1,061	0	0	666	0	395	0
* 87200500	TETHER WIRE	FOOT	1,061	0	0	666	0	395	0
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	242	0	0	0	0	242	0
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	968	0	0	0	0	968	0
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	242	0	0	0	0	242	0
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,441	0	0	0	0	1,441	0
* 87301750	ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C	FOOT	189	0	0	0	0	189	0
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	171	0	0	111	0	60	0
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	124	0	0	124	0	0	0
* 87302212	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 2C	FOOT	1,067	0	0	1,067	0	0	0
* 87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	2,357	0	0	1,372	0	985	0
* 87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	4,539	0	0	156	0	4,383	0
* 87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	4,407	0	0	3,465	0	942	0
* X8131210	ELECTRICAL CABLE AERIAL SUSPENDED, RAILROAD, NO. 14 3C	FOOT	295	0	0	0	0	295	0
* 87302650	ELECTRIC CABLE AERIAL SUSPENDED, LEAD-IN, NO. 14 1 PAIR	FOOT	1,046	0	0	0	0	1,046	0
* 87900200	DRILL EXISTING HANDHOLE	EACH	3	0	0	0	0	3	0
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3	0	0	0	0	3	0
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	0	0	2	0	0	0
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	0	0	1	0	0	0

* = SPECIALTY ITEM



USER NAME = mjp
 FILE NAME = ...2189...U-SC025.dgn
 PLOT SCALE = 1:2000 7/8"
 PLOT DATE = 3/6/2012

DESIGNED - JSM
 DRAWN - JSM
 CHECKED - DNM
 DATE - 02/06/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: 1/2"=1' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 198	SECTION 00-00045-00-PV	COUNTY LAKE	TOTAL SHEETS 195	SHEET NO. B
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	

CONTRACT NO. 63640