

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
					80% FEDERAL 20% STATE		NON-PARTICIPATING 100% LOCAL
					BICYCLE/PEDESTRIAN 0028 URBAN	TRAINEES 0042 URBAN	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	121	121		
	42001300	PROTECTIVE COAT	SQ YD	103	103		
	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	396	396		
	42400800	DETECTABLE WARNINGS	SQ FT	47	47		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	75	75		
	44000600	SIDEWALK REMOVAL	SQ FT	2,478	2,478		
	50105220	PIPE CULVERT REMOVAL	FOOT	18	18		
	50200100	STRUCTURE EXCAVATION	CU YD	519	519		
	50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	303	303		
	50300225	CONCRETE STRUCTURES	CU YD	140	140		
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,235	1,235		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9,060	9,060		
	51500100	NAME PLATES	EACH	1	1		
	54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2		
	54010604	PRECAST CONCRETE BOX CULVERTS 6' X 4'	FOOT	32	32		
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2		
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
	54247090	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	2	2		
	54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	2	2		
	542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	50	50		
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	63	63		
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	94	94		
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3		
	60107600	PIPE UNDERDRAINS 4"	FOOT	48	48		
	60107700	PIPE UNDERDRAINS 6"	FOOT	150	150		
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1		
	60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1		
	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	18	18		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	47	47		

FILE NAME = W:\Projects\2010\1008091_SouthSPEIT\cadd\Civil\Drawings\900_02.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 115 West Main Street, Suite 201
 St. Charles, Illinois 60114

USER NAME = nparr18	DESIGNED - DPB	REVISED -
PLOT SCALE = AS SHOWN	DRAWN - NDP	REVISED -
PLOT DATE = 5/11/2012	CHECKED - DPB	REVISED -
	DATE - 5/14/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. 4	OF 79 SHEETS	STA. TO STA.

F.A.P. RTE. 0336	SECTION 00-00259-00-BT	COUNTY KANE	TOTAL SHEETS 79	SHEET NO. 4
CONTRACT NO. 63667				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				