

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
					80% FEDERAL 20% STATE		NON-PARTICIPATING 100% LOCAL
					BICYCLE/PEDESTRIAN 0028 URBAN	TRAINEES 0042 URBAN	
*	6300001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	32	32		
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		
	63200310	GUARDRAIL REMOVAL	FOOT	106	106		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11		
	67100100	MOBILIZATION	L SUM	1	1		
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
*	72000100	SIGN PANEL - TYPE 1	SQ FT	72	72		
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	121	121		
*	78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73		
*	78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	213	213		
*	78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	323	323		
*	78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	143	143		
*	78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	604	604		
*	78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	35	35		
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4		
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	672	672		
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1		
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	165	165		
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	8	8		
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	112	112		
*	81028310	UNDERGROUND CONDUIT, PVC, 3/4" DIA.	FOOT	115	115		
*	81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	75	75		
*	81100100	CONDUIT ATTACHED TO STRUCTURE, 1/2" DIA., GALVANIZED STEEL	FOOT	70	70		
*	81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	250	250		
*	81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	4	4		
*	81300980	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8" X 8" X 6"	EACH	2	2		
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2,800	2,800		
*	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	185	185		

FILE NAME = \\Projects\2010\100001_South5PEIT\cadd\Civil\Drawn\Sheet\500_03.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174

USER NAME = nperria	DESIGNED - DPB	REVISED -
PLOT SCALE = AS SHOWN	DRAWN - NDP	REVISED -
PLOT DATE = 5/11/2012	CHECKED - DPB	REVISED -
	DATE - 5/14/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO. 5 OF 79 SHEETS	STA.	TO STA.

F.A.P. RTE. 0336	SECTION 00-00259-00-BT	COUNTY KANE	TOTAL SHEETS 79	SHEET NO. 5
CONTRACT NO. 63667			ILLINOIS FED. AID PROJECT	