

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
					80% FEDERAL 20% STATE		NON-PARTICIPATING 100% LOCAL
					BICYCLE/PEDESTRIAN 0028 URBAN	TRAINEES 0042 URBAN	
*	82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	1	1		
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
*	87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	1	1		
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	620	620		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	630	630		
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	740	740		
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	150	150		
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	1		
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4	4		
*	87900200	DRILL EXISTING HANDHOLE	EACH	2	2		
*	88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1		
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2		
*	88600100	DETECTOR LOOP, TYPE I	FOOT	48	48		
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	2	2		
*	89502200	MODIFY EXISTING CONTROLLER	EACH	1	1		
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1		
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1		
*	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3		
*	A2004624	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2		
*	A2005670	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	1	1		
*	B2004166	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	2	2		
*	C2005812	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	18	18		
*	C2005930	SHRUB, RHUS COPALLINA VAR LATIFOLIA MORTON (PRAIRIE FLAME SHINING SUMAC), 3' HEIGHT, BALLED AND BURLAPPED	EACH	6	6		
*	K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	3.3	3.3		
*	K0012993	PERENNIAL PLANTS, ORNAMENTAL TYPE, 3-GALLON POT	UNIT	1.6	1.6		
*	K1003660	MOWING CYCLES	EACH	10			10
	X0320622	FIELD MEASUREMENTS	L SUM	1	1		
	X0321158	PARK BENCHES	EACH	2	2		
	X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SQ FT	1,201			1,201
*	X0325170	PLANTING BED PREPARATION	SQ FT	1,364	1,364		
*	X0326629	TYPE 'G' EMERGENCY LIGHT BATTERY UNIT WALL MOUNTED	EACH	2	2		
	X0326806	WASHOUT BASIN	L SUM	1	1		
	X0327036	BIKE PATH REMOVAL	SQ YD	95	95		

FILE NAME = W:\Projects\2010\100891_Southside\PEI\road\Civil\Drawn\Sheet\800_04.dgn



USER NAME = nparris	DESIGNED - DPB	REVISED -
PLOT SCALE = AS SHOWN	DRAWN - NDP	REVISED -
PLOT DATE = 5/18/2012	CHECKED - DPB	REVISED -
	DATE - 5/14/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: AS SHOWN	SHEET NO. 6 OF 79 SHEETS STA. TO STA.

F.A.P. RTE. 0336	SECTION 00-00259-00-BT	COUNTY KANE	TOTAL SHEETS 79	SHEET NO. 6
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 63667				