

TOTAL BILL OF MATERIAL

| ITEM | UNIT | TOTAL |
|--|---------|-------|
| Structure Excavation | Cu. Yd. | 519 |
| Removal and Disposal of Unsuitable Material for Structures | Cu. Yd. | 303 |
| Concrete Structures | Cu. Yd. | 140.0 |
| Reinforcement Bars, Epoxy Coated | Pound | 9,060 |
| Name Plate | Each | 1 |
| Geocomposite Wall Drain | Sq. Yd. | 94 |
| * Porous Granular Embankment, Special | Cu. Yd. | 125 |
| * Pipe Underdrain for Structures 4" | Foot | 172 |
| * Concrete Jacking Pipe Special, Tunneled | Foot | 140 |
| * Staining Concrete Structures | Sq. Yd. | 134 |
| * Form Liner Textured Surface | Sq. Ft. | 1,235 |
| * Anti-Graffiti Protection System | Sq. Ft. | 1,201 |
| * Aluminum Railing, Special | Foot | 116 |
| * Furnish and Install Handrail | Foot | 280 |
| * Coating System for Concrete | Sq. Ft. | 3,960 |
| * Granular Subgrade Replacement | Cu. Yd. | 303 |

* Denotes a Special Provision

INDEX OF SHEETS

1. General Plan & Elevation
2. General Notes, Index of Sheets & Bill of Material
3. Tunnel Section & Details
4. Tunnel Floor Details
5. Tunnel Construction - Stage 1
6. Tunnel Construction - Stage 2
7. Tunnel Construction - Stage 3
8. Tunnel Construction - Stage 4
9. End Section Details I
10. End Section Details II
11. Undercuts at End Sections
12. End Section Railing Details
13. Architectural Details - Tunnel End Sections
14. Soil Boring Logs I
15. Soil Boring Logs II
16. Soil Boring Logs III
17. Soil Boring Logs IV
18. Soil Boring Logs V
19. Soil Boring Logs VI
20. Soil Boring Logs VII

GENERAL NOTES

1. Reinforcement bars shall conform to the requirements of ASTM A 706 Gr. 60.
2. Reinforcement bars designated (E) shall be epoxy coated.

SOUTH STREET TRAIL
BICYCLE/PEDESTRIAN UNDERPASS
BUILT 201X BY
KANE COUNTY
SEC. 00-00259-00-BT
F.A.P. RT. 0336
STRUCTURE NO. 045-3181

NAME PLATE
See Std. 515001

FILE NAME = M:\Projects\2011\0453181\Structural\Drawings\0453181-59857-002-000-00.dwg

| | | | | | | | | | | |
|---|-----------------------|----------------|-----------|---|---|---|--------------------------|---------------|-------------------|----------------|
|  WILLS BURKE KELSEY ASSOCIATES LTD. 110 West Main Street, Suite 201 St. Charles, Illinois 63174 (630) 443-7755 | USER NAME = nparris | DESIGNED - DLS | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | GENERAL NOTES, INDEX OF SHEETS & TOTAL BILL OF MATERIAL STRUCTURE NO. 045-3181 | F.A.P. RTE. = 0336 | SECTION = 00-00259-00-BT | COUNTY = KANE | TOTAL SHEETS = 79 | SHEET NO. = 30 |
| | PLOT SCALE = | DRAWN - DLS | REVISED - | | | CONTRACT NO. 63667 | | | | |
| | PLOT DATE = 5/11/2012 | CHECKED - AEU | REVISED - | | | SHEET NO. 2 OF 20 SHEETS | | | | |
| | | | | | | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |