

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				HBP FUNDING	
				80% FED 20% LAKE BARRINGTON ROADWAY	80% FED 20% LAKE BARRINGTON BRIDGE SN 049-6751
				0011 URBAN	0011 URBAN
50300300	PROTECTIVE COAT	SO YD	185		185
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1,658		1,658
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7,310		7,310
50800515	BAR SPLICERS	EACH	109		109
51200956	FURNISHING METAL SHELL PILES 12" X 0.179"	FOOT	430		430
51202305	DRIVING PILES	FOOT	430		430
51203200	TEST PILE METAL SHELLS	EACH	2		2
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	36		36
• 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50.0	50.0	
• 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	1	
• 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,600	1,600	

• DENOTES SPECIALTY ITEM

FILE NAME =	18030-SHT-50083.dgn
USER NAME =	jehrhart
PLOT SCALE =	1/1
PLOT DATE =	05/14/12

DESIGNED -	REVISOR -
DRAWN -	REVISOR -
CHECKED -	REVISOR -
DATE - 05/14/12	REVISOR -

DESIGNED -	REVISOR -
DRAWN -	REVISOR -
CHECKED -	REVISOR -
DATE - 05/14/12	REVISOR -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO. 3 OF 5 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00010-00-BR	LAKE	41	5
	SQ-3	CONTRACT NO. 63716		
[ILLINOIS] FED. AID PROJECT				