

SUMMARY OF QUANTITIES

SPECIALTY ITEMS (A)	SPECIAL PROVISION (*)	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% LOCAL 0031	100% LOCAL 0031
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	56	56	
		28000510	INLET FILTERS	EACH	2	2	
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	835	835	
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	725	725	
		35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	90	90	
		40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	46	46	
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	11	11	
		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	28	28	
		42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	338	338	
	*	42400800	DETECTABLE WARNINGS	SQ FT	24	24	
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	300	300	
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,022	1,022	
Δ	*	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2	
		60255500	MANHOLES TO BE ADJUSTED	EACH	3	3	
		60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2	2	
	*	60266600	VALVE BOXES TO BE ADJUSTED	EACH	7	7	
		67100100	MOBILIZATION	L SUM	1	1	
		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
Δ		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	100	100	
Δ		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	70	70	
Δ		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	14	14	
Δ		B2002222	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORNE), 3" CALIPER, BALLED AND BURLAPPED	EACH	4	4	
Δ		B2005726	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5	
Δ	*	Z0003850	BENCHES	EACH	4		4
		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	*	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	138	138	
Δ	*	X0300635	PLANTER	EACH	13	13	
Δ	*	X0539700	TREE FRAME AND GRATE	EACH	10	10	
	*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	8	8	
	*	X4023000	TEMPORARY ACCESS (ROAD)	EACH	3	3	
	*	X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	5,175	5,175	
	*	X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	9,588	9,588	
	*	X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	144	144	
	*	X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	1,331	1,331	
Δ	*	X8140115	HANDHOLE TO BE ADJUSTED	EACH	5	5	
Δ	*	XX000959	TRASH RECEPTACLES	EACH	4		4
	*	XX006213	METAL POST, SPECIAL	EACH	5	5	
	*	XX007824	BRICK PAVEMENT ACCENT STRIP	SQ FT	3,226	3,226	