

GENERAL NOTES

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES IN AREAS TO BE SEEDED OR SODDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE CONSTRUCTION ITEM REQUIREING THIS WORK.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF DEPARTMENT-OWNED UNDERGROUND ELECTRICAL CABLE WITHIN THE LIMITS OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR SHALL REQUEST THE ILLINOIS DEPARTMENT OF TRANSPORTATION IN OTTAWA (815-434-8417) TO LOCATE THE UNDERGROUND FACILITIES, PROVIDING A MINIMUM OF 72 HOURS NOTICE. THE DEPARTMENT IS NOT A MEMBER OF THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (JULIE) SYSTEM.

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

NOTES

"CLEAN AND PAINT WOODEN STRUCTURE"

1. NORTH AND SOUTH APPROACH SPANS:

CLEAN AND PAINT EXISTING STEEL OR WOODEN GUARDRAIL POSTS, STEEL OR WOODEN RAILS AND STEEL GUARDRAIL POST BRACKETS.

EXISTING "STRUCTURAL STEEL" ON THE APPROACHES SHALL NOT BE PAINTED.

THE CLEANING AND PAINTING OF APPROACH SPAN COMPONENTS SHALL BE AS SPECIFIED IN THE PAINT MANUFACTURER'S RECOMMENDATIONS, AND THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING WOODEN STRUCTURES" AND "CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES".

COLOR OF THE FINAL FINISH COAT FOR APPROACH SPAN COMPONENTS SHALL BE "WHITE".

2. COVERED SPAN

CLEAN AND PAINT ALL "EXISTING" INTERIOR AND EXTERIOR PAINTED PANELS AND TRIM SURFACES.

THE CLEANING AND PAINTING OF "EXISTING" INTERIOR AND EXTERIOR PAINTED PANELS AND TRIM SURFACES SHALL BE AS SPECIFIED IN THE PAINT MANUFACTURER'S RECOMMENDATIONS, THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING WOODEN STRUCTURES" AND "CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES".

COLOR OF THE FINAL FINISH COAT FOR INTERIOR AND EXTERIOR PAINTED PANELS AND TRIM SURFACES SHALL BE "BARN RED".

"PROTECTIVE COAT"

1. NORTH AND SOUTH APPROACH SPANS:

APPLY A WATERPROOFING/FIRE RETARDANT TREATMENT COAT TO ALL "UNPAINTED" SURFACES OF THE APPROACH SPANS WITH THE FOLLOWING EXCEPTION, THE SURFACE AREA OF THE APPROACH SPANS SHALL "NOT" BE TREATED.

2. COVERED SPAN:

APPLY A WATERPROOFING/FIRE RETARDANT TREATMENT COAT TO ALL "UNPAINTED" WOODEN SURFACES OF THE STRUCTURE'S INTERIOR AND EXTERIOR INCLUDING THE ROOF SHINGLES, INTERIOR OF THE COVERED SPAN AND UNDERSIDE OF THE COVERED SPANS DECK WITH THE FOLLOWING EXCEPTION, THE SURFACE AREA OF THE COVERED SPAN SHALL "NOT" BE TREATED.

COMMITMENTS

ALL EXISTING SOILS OR EMBANKMENTS DISTURBED OR EXCAVATED DUE TO THE CONTRACTOR'S CONSTRUCTION OPERATIONS SHALL REMAIN ON SITE AND SHALL BE DISPOSED OF WITHIN THE LIMITS OF THE STATE RIGHT OF WAY. THE ENGINEER SHALL DETERMINE LOCATIONS AND METHODS OF DISPOSAL AT TIME OF CONSTRUCTION.

DATE: 6-22-12

PREPARED BY: Don Bonil
DISTRICT STUDIES & PLANS ENGINEER

EXAMINED BY: Herbert K. Jones, Jr.
DISTRICT CONSTRUCTION ENGINEER

Wayne L. Phillips
DISTRICT MATERIALS ENGINEER

Bruce A. Ancker
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = woodshankr1	DESIGNED <u>RON WOODSHANK</u>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\woodshankr1\d262868	366872-shr-detailed.dgn	DRAWN <u>RON WOODSHANK</u>	REVISED -			246	(ORCBIP-2)	BUREAU	11	2	
	PLOT SCALE = 1/8" = 1'	CHECKED -	REVISED -			CONTRACT NO. 66872					
	PLOT DATE = 6/28/2012	DATE -	REVISED -			SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT