	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN 100% STATE CONST. CODE 0014 TAZEWELL COUNTY MCHD 764511
	50102400	CONCRETE REMOVAL	CUYD	1.3	1.3
	50300255	CONCRETE SUPERSTRUCTURE	CUYD	1.3	1.3
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	11,890	11,890
	67100100	MOBILIZATION	LSUM	1	1
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	LSUM	1	1
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	LSUM	1	1
	70106800	CHANGEABLE MESSAGE SIGN	CALMO	1	1
X	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1400	1400
	70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	467	467
X	78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	2392	2392
	78300100	PAVEMENT MARKING REMOVAL	SQFT	800	800
	X0323583	SPEED INDICATOR SIGN	CALDA	70	70
	Z0001903	STRUCTURAL STEEL REMOVAL	POUND	12,060	12,060
	Z0001905	STRUCTURAL STEEL REPAIR	POUND	2080	2080
	Z0003600	BEAM STRAIGHTENING	LSUM	1	1
	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1
	Z0073300	TEMPORARY SHORING AND CRIBBING	LSUM	1	1
	Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	LSUM	1	1

X SPECIALTY ITEM

FILE NAME = S:\GEN\DRAFT\STO&PLNS\SqueeBRIDGES\BRIDGE CONTRACTS\STEEL BEAM REP\68819 SN090-0091 Straighten&Strengthen.dgn	USER NAME = jonesce	DESIGNED -	REVISED -
	PLOT SCALE = 103.7051 ' / in.	DRAWN 090-0091 Straighten&Strengthen.dgn	REVISED -
	PLOT DATE = 6/20/2012	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
PINECREST DRIVE OVER F.A.I. ROUTE 74
SN 090-0091

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(90-14HB-1(BR))I-1	TAZEWELL	17	3
STEEL BEAMS REP./REPL.		CONTRACT NO. 68819		
		ILLINOIS FED. AID PROJECT		