

INDEX OF SHEETS

SHEET NO.	ITEM
1	COVER SHEET
2	INDEX OF SHEETS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	PLAN SHEETS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 5:

STD. NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
442001-04	CLASS A PATCHES
701101-02	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701451-01	RAMP CLOSURE FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2012; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND THE "SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED AT THE BROWNSTOWN WEIGH STATION ON I-70 IN FAYETTE COUNTY. THE WORK INCLUDED IN SECTION D7 PATCHING 2013-1 CONSISTS OF PAVEMENT PATCHING, PAVEMENT REMOVAL, CONTINUOUSLY REINFORCED PCC PAVEMENT, PAVEMENT MARKING, TRAFFIC CONTROL, AND ANY OTHER WORK NECESSARY TO COMPLETE THIS PROJECT.

THE PAVEMENT REMOVAL WILL BE THE EXISTING 8" PCC PAVEMENT AND EXISTING STABILIZED SUB-BASE 4". THE AREA OF PAVEMENT REMOVAL SHALL BE REPLACED WITH CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12". THE ADDITIONAL EXCAVATION REQUIRED FOR THE 12" PAVEMENT SHALL BE INCLUDED IN THE COST OF THE PAVEMENT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE PAVEMENT PATCHES ARE CLASS A AND THE TYPE IS SPECIFIED ON THE PLANS. THE PATCHES ARE AT VARIOUS LOCATIONS ON THE RAMP AND WILL BE LAID OUT BY THE ENGINEER IN THE FIELD.

THE SAW CUTS REQUIRED FOR THE PAVEMENT REMOVAL SHALL BE INCLUDED IN THE COST OF THE PAVEMENT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

PAVEMENT MARKING SHALL BE APPLIED IN ACCORDANCE WITH SECTION 780 OF THE STANDARD SPECIFICATIONS.

PERMANENT PAVEMENT MARKING ON THIS PROJECT SHALL BE MODIFIED URETHANE PAVEMENT MARKING OF THE SIZE AND TYPE SPECIFIED IN THESE GENERAL NOTES.

THE TOTAL QUANTITY OF MODIFIED URETHANE PAVEMENT MARKING - LINE 4" CONSISTS OF 600 FEET OF WHITE AND 600 FEET OF YELLOW.

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS AND GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\p\work\p\d01\st\staffennk\d030488910	74577-st-index.dgn	DRAWN -	REVISED -			TO	D7 PATCHING 2013-1	FAYETTE	5	2	
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			SCALE: N/A		SHEET 1 OF 1 SHEETS		STA. TO STA.	
	PLOT DATE = 5/3/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					