

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE		
				0005		
42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	867	867		
42100615	PAVEMENT REINFORCEMENT	SQ YD	867	867		
44000100	PAVEMENT REMOVAL	SQ YD	867	867		
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	8	8		
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	29	29		
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	20	20		
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	186	186		
44213000	PATCHING REINFORCEMENT	SQ YD	243	243		
44213200	SAW CUTS	FOOT	665	665		
44213204	TIE BARS 3/4"	EACH	368	368		
67100100	MOBILIZATION	L SUM	1	1		
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1		
X 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	1200	1200		

X SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
c:\pwwork\pilot\staffennk\0304889\0	74577-4h1-soq.dgn	DRAWN -	REVISED -		SCALE: N/A	SHEET 1	OF 1	SHEETS	STA.	TO STA.	70	07 PATCHING 2013-1	FAYETTE	5	3
	PLOT SCALE = 100.0000 / 1 in.	CHECKED -	REVISED -												
	PLOT DATE = 5/3/2012	DATE -	REVISED -												

ILLINOIS FED. AID PROJECT