

INDEX OF SHEETS

SHT NO	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	PLAN SHEET, TYPICAL
5	DETOUR SHEET

GENERAL NOTES

- FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:
 ALL HOT MIX ASPHALT 2.016 TONS/CU YD
 ALL AGGREGATE 2.05 TONS/CU YD
 BITUMINOUS MATERIALS:
 ON PAVEMENT 0.09 GAL/SQ YD
 INTERMEDIATE LIFTS (FOG COATS) 0.04 GAL/SQ YD
 ON AGGREGATE SURFACE 0.32 GAL/SQ YD
 AGGREGATE (PRIME COAT) 0.0015 TONS/SQ YD
 RIPRAP 1.50 TONS/CU YD
- PROTECTIVE COAT SHALL BE APPLIED TO PCC PAVEMENT AS NEEDED ACCORDING TO THE SEASONAL REQUIREMENTS FOR ARTICLE 420.18 OF THE STANDARD SPECIFICATIONS.
- NEW PAVEMENT CONSTRUCTED ADJACENT TO EXISTING PAVEMENT SHALL BE TIED TO EXISTING UTILIZING TIE BARS OF THE SAME SIZE AND SPACING SHOWN AT THE CENTERLINE ON STANDARD 420101. THE TIE BARS SHALL BE INCLUDED IN THE COST OF THE PROPOSED PAVEMENT.
- THE PROPOSED PAVEMENT SHALL BE CONSTRUCTED PER HIGHWAY STANDARD 420101 EXCEPT STABILIZED SUB BASE WILL NOT BE REQUIRED.

STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
420101-04	24' JOINTED PCC PAVEMENT
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS
B.L.R. 21-9	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

COMMITMENTS

THE FOLLOWING ADMINISTRATORS SHOULD BE NOTIFIED WHEN THE EXACT DATES OF CLOSURE ON US 45 ARE KNOWN :

CLIFF KARNES - NCOE SCHOOL DISTRICT SUPERINTENDENT (618) 599-0058
 MATT VOLLMAN - NCOE HIGH SCHOOL PRINCIPAL (618) 499-3909
 WAYNE MCKINSEY - WHITE COUNTY EMERGENCY DISPATCHER (618) 382-4633
 BRIAN RAY - WHITE COUNTY ENGINEER (618) 382-4811

Prepared By:	<i>Joe G. [Signature]</i> DISTRICT STUDIES & PLANS ENGINEER
Examined By:	<i>Justin E. [Signature]</i> DISTRICT LAND ACQUISITION ENGINEER
Examined By:	<i>Chris Nelson [Signature]</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
Examined By:	<i>Will Kelly [Signature]</i> DISTRICT OPERATIONS ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT PROJECT IMPLEMENTATION ENGINEER
Examined By:	<i>Douglas Halfon [Signature]</i> DISTRICT CONSTRUCTION ENGINEER
Examined By:	<i>Bruce [Signature]</i> DISTRICT MATERIALS ENGINEER
Approved By:	<i>Omara [Signature]</i> DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER
DATE	May 11 2012

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
or\pwork\pwork\russell\of\0302059\78300-stds-plandgn	russellof	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	332 09 CM SLOPE REPAIR 2013-	WHITE	5	2
		CHECKED -	REVISED -											
		DATE	REVISED -											

ILLINOIS FED. AID PROJECT