

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE		0004
		UNIT	TOTAL QUANTITY	ROADWAY 100% STATE
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A-6"	SO YD	870	870
42000501	PORTLAND CEMENT CONCRETE 10" (JOINTED)	SO YD	805	805
42001300	PROTECTIVE COAT	SOYD	805	805
44000100	PAVEMENT REMOVAL	SO YD	805	805
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	11	11
67100100	MOBILIZATION	L SUM	1	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3
X 72000100	SIGN PANEL, TYPE 1	SQ FT	74.5	74.5
X 72000200	SIGN PANEL, TYPE 2	SQ FT	112	112
X 78001110	PAINT PAVEMENT MARKINGS - LINE 4"	FOOT	652	652

X SPECIALTY  
ITEM

FILE NAME *	USER NAME * russellof	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\pwork\pndot\russellof\48382851\7839-shr-plan.dgn	39-shr-plan.dgn	DRAWN -	REVISED -						332 09 CM SLOPE REPAIR 2013-	WHITE	5	3	
PLOT SCALE * 1/8"=1'-0"		CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 78300		
PLOT DATE * 5/16/2012		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								