

**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM	UNIT	CONSTRUCTION TYPE CODE 0014
			TOTAL QUANTITY
# 20200100	EARTH EXCAVATION	CU YD	150
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	80
21101025	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	590
25000210	SEEDING, CLASS 2A	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18
25100050	EROSION CONTROL BLANKET	SQ YD	590
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40
28000305	TEMPORARY DITCH CHECKS	FOOT	40
28000400	PERIMETER EROSION BARRIER	FOOT	82
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	80
28200200	FILTER FABRIC	SQ YD	80
# 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	85
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	139
40600200	AGGREGATE (PRIME COAT)	TON	2
40603080	HOT MIX ASPHALT BINDER COURSE, IL-19 D, N50	TON	98.5
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	39.3
44000100	PAVEMENT REMOVAL	SQ YD	222
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	43
# 50300280	CONCRETE ENCASEMENT	CU YD	8.7
50300300	PROTECTIVE COAT	SQ YD	185
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1378
# 50700105	TREATED TIMBER	F.B.M.	200
# 50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	60
# 50901050	STEEL RAILING, TYPE SM	FOOT	86
# 51500100	NAME PLATES	EACH	1
# 58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	153
# 58300100	PORTLAND CEMENT MORTAR FINISH COURSE	FOOT	301

\* INDICATES SPECIALTY ITEM

CODE NUMBER	PAY ITEM	UNIT	CONSTRUCTION TYPE CODE 0014
			TOTAL QUANTITY
# 87100100	MOBILIZATION	L SUM	1
X7401216	TRAFFIC CONTROL AND PROTECTION (Special)	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	12
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8
20012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	100
20030850	TEMPORARY INFORMATION SIGNING	SQ FT	52
X0325740	FIBER WRAP	SQ FT	250
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	180

\* INDICATES SPECIALTY ITEM

**NOTES:**

- ITEMS 50700105 AND 58300100 ARE CONTINGENCY ITEMS AND QUANTITIES MAY BE REDUCED OR ELIMINATED BASED ON FIELD CONDITIONS.

CORRECTED: 2012.05.14 10:47:41 AM C:\Users\woodman\OneDrive\Documents\110638-500.dwg  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 18350E AVENUE - DEKALB COUNTY, ILLINOIS 62521-2702  
 FAX: 314.233.7702



DESIGNED - CAC	REVISED -
DRAWN - BCD	REVISED -
CHECKED - TAO	REVISED -
DATE - 05/17/12	FILE - 110638-500.dwg

**VILLAGE OF KIRKLAND  
HORTENSE ST BRIDGE OVER  
BULL RUN CREEK**

**SUMMARY OF QUANTITIES**

SCALE: NONE STA. TO STA.

MUN. ST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1090	10-00008-00-BR	DEKALB	20	4
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT			CONTRACT NO. 87532 RRP-037043	