



- ① Dowel Rods to be grouted after beams are in place and allowed to cure (Min. 24 hr.) prior to grouting the shear keys.
- ② 1" Joint shall be packed with a very dry mix of 2:1 sand and P.C. mortar. 1" Dimension may vary plus or minus to accommodate tolerance in beam lengths.

**RAIL POST SPACING AND  
SUPERSTRUCTURE DETAILS  
PIKE COUNTY  
SECTION 10-00085-00-BR  
C.H. 10 OVER BAY CREEK TRIBUTARY**

SHEET NO. 7  12 SHEETS	ROUTE NO. CH 10	SECTION 10-00085-00-BR	COUNTY PIKE	TOTAL SHEETS 23	SHEET NO. 13
	S.N. 075-3323		CONTRACT NO. 93582		
FED. ROAD DIST. NO. 7 ILLINOIS			FED. AID PROJECT BRS-0603(115)		