



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 18, 2018

SUBJECT: Route FAS 557 (CH 25)  
Section 14-00035-03-RS  
Logan County  
Contract No. 93717  
Item 56  
August 3, 2018 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### 1. Revised page 2 of the special provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.  
Bureau Chief  
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

**TRAFFIC CONTROL PLAN**

Traffic control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, these Special Provisions, any special details and Highway Standards contained herein and in the plans.

Special attention is called to Sections 107 and 701 through 705 of the Standard Specifications for Road and Bridge Construction, and as amended by the Supplemental Specifications, Recurring Special Provisions, the Special Provisions contained herein, and the following traffic control related (1) Highway Standards; (2) Supplemental Specifications and Recurring Special Provisions (3) Other Special Provisions which are included in this contract:

- 1) Highway Standards
  - a) Standard 701001
  - b) Standard 701006
  - c) Standard 701306
  - d) Standard 701311
  - e) Standard 701326
  - f) Standard 701901
  - g) Standard BLR 21
  
- 2) Supplemental Specifications and Recurring Special Provisions:
  - a) Work Zone Traffic Control Surveillance
  - b) Flaggers in Work Zones
  
- 3) Special Provisions:
  - a) Automated Flagger Assistance Device
  - b) Construction and Maintenance Signs

Limitations of Construction. The Contractor shall coordinate the items of work in order to keep hazards and traffic inconveniences to a minimum, as specified below.

1. The contractor shall provide, erect, and maintain all the necessary barricades, cones, drums, flags and lights for the warning and protection of traffic, as required by Section 107 and 701 through 703 of the Standard Specifications.

2. In addition to the signs required by the various traffic control standards, the Contractor shall erect ROAD CONSTRUCTION NEXT X MILES (G20-1140(0)6036), and NO PASSING ZONES NOT STRIPED NEXT X MILES (G20-1100(0)6036) signs on CH 25 at both ends of the project.

3. General: Signposts shall be 100 x 100 mm (4 x 4 inches) wood posts according to Article 1007.05. All posts shall be braced to the satisfaction of the Engineer. The use of metal posts will not be permitted.
  
4. All advance warning signs shall be in new or like new condition at the start of the project. All warning signs shall be 48 inches by 48 inches and have a black legend on a fluorescent orange reflectorized background.