

COMPANY NAME: #0000000000
 PROJECT CONTACT: #0000000000
 CLIENT: #0000000000
 #DATE# #TIME#
 #FILE#

PROFILE SURVEYED
 DATE
 NOTE BOOK
 NO. OF WAY CHECKED
 STRUCTURE NOTATIONS CHFD

PLAN SURVEYED
 DATE
 NOTE BOOK
 NO. OF WAY CHECKED
 STRUCTURE NOTATIONS CHFD

80% 100%
 20% 50% 100%
 TIME

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	1000-2A	SFTY-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	268	268	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	559	559	
20200100	EARTH EXCAVATION	CU YD	78371	78371	
20700110	POROUS GRANULAR EMBANKMENT	TON	1015	1015	
20800150	TRENCH BACKFILL	CU YD	892	892	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	49500	49500	
25000100	SEEDING, CLASS 1	ACRE	7.2	7.2	
25000200	SEEDING, CLASS 2	ACRE	33.4	33.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3006	3006	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3006	3006	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3006	3006	
25100115	MULCH, METHOD 2	ACRE	40.6	40.6	
25100830	EROSION CONTROL BLANKET	SQ YD	2348	2348	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20300	20300	
28000300	TEMPORARY DITCH CHECKS	EACH	286	286	
28000400	PERIMETER EROSION BARRIER	FOOT	4800	4800	
28000500	INLET AND PIPE PROTECTION	EACH	100	100	
28100907	STONE DUMPED RIPRAP, CLASS A4	TON	1101	1101	
28200200	FILTER FABRIC	SQ YD	1209	1209	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	12363	12363	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	2047	2047	
31100300	AGGREGATE BASE COURSE, TYPE B 8"	TON	1989	1989	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1989	1989	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	10156	10156	
40600300	AGGREGATE (PRIME COAT)	TON	188.4	188.2	0.2
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	728	728	
40600990	TEMPORARY RAMP	SQ YD	114	114	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	218	218	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	588	588	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	210	210	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	82883	82883	76
44000100	PAVEMENT REMOVAL	SQ YD	4185	4185	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1780	1780	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	2245	2245	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	12612	12568	14
44201165	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	979	979	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	386	386	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1195	1195	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	11771	11759	12
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	SQ YD	22730	22709	21
60105200	REMOVE EXISTING CULVERTS	EACH	64	64	
60800105	REINFORCEMENT BARS	POUND	5310	5310	
64001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2	
64001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2	
64001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2	2	
64001005	BOX CULVERT END SECTION, CULVERT NO. 5	EACH	2	2	
64001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	2	2	
64003000	CONCRETE BOX CULVERTS	CU YD	24	24	
64010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	54.0	54.0	
64010804	PRECAST CONCRETE BOX CULVERT 9' X 4'	FOOT	102.0	102.0	
64011004	PRECAST CONCRETE BOX CULVERT 10' X 4'	FOOT	54.0	54.0	
642A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	440	440	
642D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	2024	2024	
642D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	195	195	
642D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	60	60	
642D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	170	170	
642D5485	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	52	52	
64207573	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND - SIZE 18"	FOOT	326	326	
64207591	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND - SIZE 36"	FOOT	219	219	
64213453	END SECTIONS 18"	EACH	76	76	
64213459	END SECTIONS 24"	EACH	6	6	
64213465	END SECTIONS 30"	EACH	2	2	
64213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5	
64213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	12	12	
64213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
64214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8	8	
64214305	END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2	

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.S. 1517 (U.S. ROUTE 150)
 SUMMARY OF QUANTITIES
 (SHEET 1 OF 2)

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

F.A.S. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517 (2)RS-3 (3)RS-4	MCLEAN	223	4
STA. TO STA.	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

66383

REVIS
 7-17-06