

COMPANY NAME: #COMPANY NAME#
 PROJECT CONTACT: #PROJECT_CONTACT#
 CLIENT: #CLIENT#
 #DATE# #TIME#
 #FILES#

PROFILE SURVEYED
 GRADES CHECKED
 NOTE BOOK
 NO. NOTED
 PROJECT NO. NOTARY'S CHRG.
 NO.

PLAN SURVEYED
 ALIGNMENT CHECKED
 NO. FILE NAME
 NO.

← 80% 80% STAKE →

| CODE NUMBER | PAY ITEMS | UNIT | TOTAL QUANTITY | 1000-2A | SFTY-2A |
|-------------|---|--------|----------------|---------|---------|
| 54214923 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 18" | EACH | 6 | 6 | |
| 54214941 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 36" | EACH | 8 | 8 | |
| 54247130 | GRATING FOR CONCRETE FLARED END SECTION 24" | EACH | 2 | 2 | |
| 54248160 | GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36" | EACH | 8 | 8 | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1, 12" | FOOT | 771 | 771 | |
| 550A0070 | STORM SEWERS, CLASS A, TYPE 1, 15" | FOOT | 500 | 500 | |
| 550A0090 | STORM SEWERS, CLASS A, TYPE 1, 18" | FOOT | 688 | 688 | |
| 550A0120 | STORM SEWERS, CLASS A, TYPE 1, 24" | FOOT | 106 | 106 | |
| 60218400 | MANHOLES, TYPE A, 4-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 7 | 7 | |
| 60220230 | MANHOLES, TYPE A, 4-DIAMETER, SPECIAL FRAME AND GRATE | EACH | 6 | 6 | |
| 60235700 | INLETS, TYPE A, TYPE 3 FRAME AND GRATE | EACH | 2 | 2 | |
| 60236200 | INLETS, TYPE A, TYPE 8 GRATE | EACH | 2 | 2 | |
| 60238700 | INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE | EACH | 12 | 12 | |
| 60240301 | INLETS, TYPE B, TYPE 8 GRATE | EACH | 1 | 1 | |
| 60240385 | INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE | EACH | 10 | 10 | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 1 | 1 | |
| 60500050 | REMOVING CATCH BASINS | EACH | 2 | 2 | |
| 60500060 | REMOVING INLETS | EACH | 2 | 2 | |
| 60600005 | CONCRETE CURBS, TYPE B | FOOT | 200 | 200 | |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 6858 | 6858 | |
| 61133100 | FIELD TILE JUNCTION VAULTS, 2' DIA. | EACH | 60 | 60 | |
| 61139800 | STORM SEWERS, SPECIAL 4" | FOOT | 600 | 600 | |
| 61139900 | STORM SEWERS, SPECIAL 6" | FOOT | 600 | 600 | |
| 61140000 | STORM SEWERS, SPECIAL 8" | FOOT | 600 | 600 | |
| 61140100 | STORM SEWERS, SPECIAL 10" | FOOT | 600 | 600 | |
| 61140200 | STORM SEWERS, SPECIAL 12" | FOOT | 600 | 600 | |
| 63000005 | STEEL PLATE BEAM GUARD RAIL, TYPE B | FOOT | 100 | 100 | |
| 63100087 | TRAFFIC BARRIER TERMINAL, TYPE 6A | EACH | 2 | 2 | |
| 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 1 | 1 | |
| 63100169 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) | EACH | 1 | 1 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 163 | 163 | |
| 64002000 | NON-SPECIAL WASTE DISPOSAL | CYD | 42 | 42 | |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 166 | 166 | |
| 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | 1 | |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE 1 | EACH | 44 | 44 | |
| 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 2 | 2 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 12 | 12 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 20 | 20 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 10686 | 10686 | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 36 | 36 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 243843 | 243843 | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 24060 | 24060 | |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 258 | 258 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 32430 | 32430 | |
| 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 372 | 372 | |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 10 | 10 | |
| 72400800 | RELOCATE SIGN PANEL ASSEMBLY - TYPE B | EACH | 3 | 3 | |
| 72500100 | OBJECT MARKER - TYPE 1 | EACH | 2 | 2 | |
| 73000100 | WOOD SIGN SUPPORT | FOOT | 1010 | 1010 | |
| 73502000 | RELOCATE GROUND MOUNTED SIGN SUPPORT | EACH | 16 | 16 | |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 36 | 36 | |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 81281 | 81281 | |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 8020 | 8020 | |
| 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 156 | 156 | |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 281 | 281 | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 437 | 437 | |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 10 | 10 | |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 2 | 2 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 450 | 450 | |
| X3550215 | BITUMINOUS BASE COURSE SUPERPAVE 5 3/4" | SQ YD | 4921 | 4921 | |
| X3560130 | BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH | SQ YD | 2266 | 2266 | |
| X4086414 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 | TON | 9862 | 9862 | |
| X4086814 | BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 | TON | 621 | 621 | |
| X4086765 | LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50 | TON | 8274 | 8274 | |
| X8083800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE III-4.24 | FOOT | 154 | 154 | |
| Z0000990 | AGGREGATE FOR TEMPORARY ACCESS | TON | 2900 | 2900 | |
| Z0064225 | SEALING ABANDONED WATER WELLS | EACH | 1 | 1 | |
| X0325321 | PRECAST CONCRETE BOX CULVERT 6' X 2.5' | FOOT | 54.0 | 54.0 | |
| X0325331 | PRECAST CONCRETE BOX CULVERT 8' X 3.5' | FOOT | 54.0 | 54.0 | |

REVISIONS
 7-17-06

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.S. 1517 (U.S. ROUTE 150)
 SUMMARY OF QUANTITIES
 (SHEET 2 OF 2)
 SCALE: VERT. 1"=40'
 HORIZ. 1"=40'
 DATE: 7-17-06
 DRAWN BY: []
 CHECKED BY: []

| | | | | |
|---------------------|-----------------|------------------|--------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1517 | (2)RS-3 (3)RS-4 | MCLEAN | 223 | 5 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |