

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	(2)RS-3 (3)RS-4	MCLEAN	223	24
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

66383

LOCATION	SUBBASE * GRANULAR MAT. TYPE A, 4" (SQ YD)	AGGREGATE BASE COURSE TYPE B, 8" (SQ YD)	AGGREGATE SURFACE COURSE TYPE B (TON)	AGGREGATE FOR TEMPORARY ACCESS (TON)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	AGGREGATE (PRIME COAT) (TON)	BITUMINOUS SURFACE REM. (VAR. DEPTH) (SQ YD)	BITUMINOUS SURFACE REM. BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	PCC DRIVEWAY PAVEMENT 6" (SQ YD)	PCC DRIVEWAY PAVEMENT 8" (SQ YD)	INCIDENTAL BITUMINOUS SURFACING (TON)	PAVEMENT REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
U.S. ROUTE 150														
408+02.77 TO 419+83.00	1543				231	5.8	1179	147	29					
419+83.00 TO 438+84.82	2159				372	9.3	3606							
438+84.82 TO 449+81.00					215	5.4	2680							
449+81.00 TO 471+70.00					429	10.8	5351							
471+70.00 TO 483+42.00					230	5.8	2865							
483+42.00 TO 489+48.00					119	3.0	1482							
489+48.00 TO 498+23.00					172	4.3	2139							
498+23.00 TO 502+75.00					89	2.3	1105							
502+75.00 TO 513+33.00					207	5.2	2587							
513+33.00 TO 523+63.00					202	5.1	2518							
523+63.00 TO 535+41.00					231	5.8	2880							
535+41.00 TO 618+52.00					1626	40.7	20316							
618+52.00 TO 630+10.00					227	5.7	2831							
630+10.00 TO 638+81.00					171	4.3	2130							
638+81.00 TO 647+69.00					174	4.4	2171							
647+69.00 TO 678+04.00					594	14.9	7419							
678+04.00 TO 689+51.00					225	5.7	2804							
689+51.00 TO 705+84.00					320	8.0	3992							
705+84.00 TO 717+82.00					235	5.9	2929							
717+82.00 TO 736+20.00					360	9.0	4493							
736+20.00 TO 746+08.00					194	4.9	2416							
746+08.00 TO 754+51.18					165	4.2	2062	147	25					
SUBTOTAL	3702	0	0	0	6788	170.5	81955	294	54	0	0	0	0	0
SEMINARY STREET														
1100+00.00 TO 1101+31.14	49				47	1.2	576							
DOOLEY AVENUE		348			131	0.7						35.6	418	
OAK STREET													283	
C.H. 36 NORTH														
1203+00.00 TO 1210+00.00	1715				798	4.3		123	13				1610	
T.R. 2075														
1300+20.00 TO 1306+43.18	1357				734	3.9	428		18				500	
C.H. 36 SOUTH														
1500+00.00 TO 1502+56.21	1205				417	2.3							733	
T.R. 2200														
1601+00.00 TO 1602+98.36	886				285	1.6							571	
T.R. 2325														
1700+00.00 TO 1702+50.00	576				34	0.9		89	9					
T.R. 2375														
1800+50.00 TO 1802+39.72	355				34	0.9		116	9					
T.R. 2400														
1900+00.00 TO 1901+50.00	282				31	0.8		106	11					
T.R. 2450														
2400+50.00 TO 2402+32.08	756				239	1.3							70	
SUBTOTAL - SIDEROADS	7181	348	0	0	2750	17.9	1004	434	60	0	0	35.6	4185	0
DRIVEWAYS														
SUBTOTAL**	0	1699	1989.0	2905.7	618	0	0	0	0	588	210	182.1	0	1780
TOTAL	10883	2047	1989.0	2905.7	10156	188.4	82959	726	114	588	210	217.7	4185	1780

* PAVEMENT PATCHING AND ASSOCIATED SUBBASE GRANULAR MATERIAL TYPE A, 4" NOT INCLUDED. SEE PATCHING SCHEDULE FOR QUANTITIES AND LOCATIONS.
 ** SEE DRIVEWAY SCHEDULE FOR INDIVIDUAL DRIVEWAY QUANTITIES.

PLAN SURVEYED BY DATE
 NOTE BOOK NO. CHECKED BY
 REVISIONS

PROFILE SURVEYED BY DATE
 NOTE BOOK NO. CHECKED BY
 REVISIONS

COMPANY NAME: SEC. INC.
 PROJECT CONTACT: TONY SIMMONS
 CLIENT: DOT
 7/14/2006 9:55:00 AM
 F:\Jobs\Smith\2006\0002\01\cadd\11-dwg\11-dwg\24-pave.dgn

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.S. 1517 (U.S. ROUTE 150)
PAVEMENT SCHEDULE
(SHEET 1 OF 2)

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

REVISED
7-17-06
SHEETS