



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 27, 2023

SUBJECT FAS Route 1858 (IL 155)
Section (108R)RS-5
Randolph County
Contract No. 76R65

Item No. 54, August 4th, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices
2. Revised page i of the Table of Contents of the Special Provisions
3. Revised pages 3 and 5 of the Special Provisions
4. Revised sheets 2-9 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT..... 1
DESCRIPTION OF PROJECT..... 1
SUBMITTAL OF EEO/LABOR DOCUMENTATION..... 1
~~GUARDRAIL REMOVAL..... 3~~
TRAFFIC CONTROL PLAN..... 4
TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)..... 4
WIDTH RESTRICTION SIGNING..... 4
~~PLUG EXISTING INLETS..... 5~~
BRIDGE DECK SCARIFICATION 1 1/2"..... 5
STATUS OF UTILITIES TO BE ADJUSTED..... 11
DECK SLAB REPAIR..... 12
BAR SPLICERS..... 17
TEMPORARY SUPPORT SYSTEM..... 17
CONCRETE WEARING SURFACE..... 18
BLENDED FINELY DIVIDED MINERALS (BDE)..... 20
COMPENSABLE DELAY COSTS (BDE)..... 20
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 23
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)..... 32
PERFORMANCE GRADED ASPHALT BINDER (BDE)..... 32
PORTLAND CEMENT CONCRETE (BDE)..... 37
STEEL COST ADJUSTMENT (BDE)..... 37
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)..... 39
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... 40
SUBMISSION OF PAYROLL RECORDS (BDE)..... 40
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)..... 41
WEEKLY DBE TRUCKING REPORTS (BDE)..... 42
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 42
WORKING DAYS (BDE)..... 44



The ORIGINAL and one copy of the Request for Approval of Subcontractor (FORM BC 260A) shall be submitted to the District at the IDOT Preconstruction Conference.

SUBSTANCE ABUSE PREVENTION PROGRAM CERTIFICATION:

The ORIGINAL and one copy of the Substance Abuse Prevention Program Certification (FORM BC 261) shall be submitted to the District at the IDOT Preconstruction Conference.

The Contractor is required to follow submittal procedures as provided by the EEO Officer at the preconstruction conference and to follow all revisions to those procedures as issued thereafter.

If a report is rejected, it is the Contractor’s responsibility to make required adjustments and/or corrections and resubmit the report. Reports not submitted and accepted within the established timeframes will be considered late.

Disclosure of this information is necessary to accomplish the statutory purpose as outlined under 23CFR part 230 and 41CFR part 60.4 and the Illinois Human Rights Act. Disclosure of this information is REQUIRED. **Failure to comply with this special provision may result in the withholding of payments to the Contractor and/or cancellation, termination, or suspension of the contract in whole or part.**

This special provision must be included in each subcontract agreement.

ALL HARD COPY FORMS TO BE SUBMITTED TO:

Region 5 Engineer
Illinois Department of Transportation
ATTN: EEO/LABOR OFFICE
1102 Eastport Plaza Drive
Collinsville, IL 62234-6198

Compliance with this special provision shall be included in the cost of the contract, and no additional compensation will be allowed for any costs incurred.



~~GUARDRAIL REMOVAL~~

~~Effective: February 11, 1981~~ ~~Revised: November 1, 2006~~

~~This work shall be done in accordance with Section 632 of the Standard Specifications, except as herein modified.~~

~~The salvaged material shall be hauled to the _____ Sector Maintenance Yard for storage.~~

~~Basis Of Payment: This work will be paid for at the contract unit price per FOOT for GUARDRAIL REMOVAL.~~

This work will be paid for at the contract unit price per LUMP SUM for WIDTH RESTRICTION SIGNING.

~~PLUG EXISTING INLETS~~

~~This work shall be to plug existing inlets at the locations shown on the plans.~~

~~Equipment: The equipment used shall be subject to the approval of the Engineer and shall allow for the Contractor to effectively fill the existing inlets with controlled low strength material mix 1 or a concrete mix approved by the Engineer prior to the beginning of construction. The method for plugging the inlets to allow the material to be used for filling the existing inlet shall be the responsibility of the Contractor.~~

~~Construction Requirements: Sidewalks, curbs, drains, reinforcement, and/or existing transverse and longitudinal joints which are to remain in place shall be protected from damage during operations. All damage caused by the Contractor shall be corrected, at the Contractor's expense, to the satisfaction of the Engineer.~~

~~The Contractor shall control the use of the material used for filling the existing inlets to ensure it does not overflow or be spilled onto the bridge deck or pavement.~~

~~The filling of the inlets shall be done in a manner that allows the fill material to reach set prior to filling the inlet with concrete used for concrete structures to create a curb at the inlet.~~

~~Method of Measurement: The work will be measured per each. No additional payment will be made.~~

~~Basis of Payment: This work will be paid for at the contract unit price per EACH for PLUG EXISTING INLETS.~~

1

BRIDGE DECK SCARIFICATION 1 1/2"

This work shall also include the scarification of the existing deck 1 1/2" to expose the top mat of reinforcement, partial depth patching, and surface preparations to the specifications and in accordance with plan details.

Equipment: The equipment used shall be subject to the approval of the Engineer and shall meet the following requirements:

- (a) Surface Preparation Equipment. Surface preparation equipment shall be according to the applicable portions of Section 1100 and the following:
 - (1) Sawing Equipment. Sawing equipment shall be a concrete saw capable of sawing concrete to the specified depth.
 - (2) Mechanical Blast Cleaning Equipment. Mechanical blast cleaning may be performed by high-pressure waterblasting or shotblasting. Mechanical blast cleaning equipment

Revised 7-27-2023