



Location Map

NOTE:

Traffic Control Devices for township road closures during construction shall be in Accordance with IDOT Standard 702001 and approved by Danny Lock, Joshua Township road commissioner. (309-338-2276)

Summary of Quantities					
#	Item	Section	Quantity	Unit	Rates/Remarks
1	Special Clearing	201	1	L.S.	
2	Mine Refuse Excavation	202	33,135	C.Y.	
3	Stone Riprap A-3	IDOT 281	897	Ton	
4	Stone Riprap CA-1	IDOT 281	41.7	Ton	
5	Pipe Culvert 30" Dia., Corrugated PE with Smooth Interior, Type 1	IDOT 542	40	Foot	
6	Pipe Culvert 36" Dia., Corrugated PE with Smooth Interior, Type 1	IDOT 542	44	Foot	
7	Mobilization (Max. 6% of Bid)	671	1	L.S.	
8	Traffic Control and Protection - Standard 702001	701	1	L.S.	Type III Barricade

GENERAL NOTES

The contractor is responsible for visiting the site and familiarizing himself with the existing conditions and the proposed reclamation work prior to submitting a bid.

The contractor shall provide and pay for all field engineering services to execute the project as specified in the Field Engineering section of the Special Provisions.

The contractor is responsible for locating and protecting all existing utility lines pertaining to the work.

Unless noted on the plans, all onsite access roads may be used for construction and must be maintained during construction and restored to original or better condition at the completion of work by the contractor. Access roads to the site as designated in the plans are to be maintained to the satisfaction of the engineer.

The construction limits will be staked by the contractor prior to construction. The contractor is responsible for the repair and or restitution at his own expense for all damages done to any area outside the construction limits.

CONSTRUCTION NOTES

BURIAL/REMOVAL OF MATERIAL—Concrete and masonry debris designated for burial by the engineer shall be buried at least three feet below proposed final grade. Onsite organic debris and trash shall be disposed of in an engineer approved offsite landfill in accordance with Sections 201 and 501 of the Special Provisions.

TREE REMOVAL—Trees removed shall be disposed of onsite per Section 201 of the Special Provisions.

EROSION CONTROL—The contractor shall schedule his operations and take such precautions that may be necessary to prevent or minimize erosion. Failure to comply with this requirement shall cause the contractor to be fully responsible for repairing any eroded areas and cleaning up areas or drainage structures that have become silted in or damaged.

State of Illinois
Department of Natural Resources

Red Ember - Sediment Control
Reclamation Project
AML-GFuE-0406
Fulton County

Drawn By: T.M.
Checked By: _____
Date: 06/30/05

Summary of Quantities/
General Notes/Location Map
Sheet
2 of 24