

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1316RS-1		COOK	22	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	30	30			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4			
40600300	AGGREGATE (PRIME COAT)	TON	19	19			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	75	75			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	385	385			
44000116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD	1718	1718			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2300	2300			
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	105	105			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	282	282			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	59	59			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1222	1222			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5276	5276			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	370	370			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2			
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2			
60260100	INLETS TO BE ADJUSTED	EACH	2	2			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000			CONTRACT NO. 60754
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	983	983			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	210	210			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6545	6545			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	300	300			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	140	140			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	62	62			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3038	3038			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6545	6545			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	140	140			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	62	62			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100			
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	246	246			
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	20	20			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	781	781			
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	390	390			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	9222	9222			

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHERMER ROAD
WILLOW RD. TO OLD WILLOW RD.

PLOT DATE: 4/5/2005