

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
STAGE IA				
MOT-4				
4"	4" SOLID (Y)	2352+00	2367+00	1500
4"	6'S - 2'D (W)	2359+50	2362+53	76
4"	4" SOLID (W)	2354+35	2367+00	1265
4"	4" SOLID (Y)	2367+00	2382+00	1500
4"	4" SOLID (W)	2367+00	2372+14	514
4"	4" SOLID (Y)	2367+52	2374+60	708
4"	4" SOLID (W)	2367+52	2382+00	1448
5"	5" 30'S - 10'D	2364+04	2367+00	74
5"	5" 30'S - 10'D	2367+00	2382+00	375
12"	12" SOLID (W)	2354+35	2359+50	313
12"	12" SOLID (W)	2364+04	2367+52	202
MOT-5				
4"	4" SOLID (Y)	4381+76	4397+07	1531
4"	4" SOLID (W)	4381+76	4389+83	807
4"	4" SOLID (Y)	4384+24	4389+83	559
4"	4" SOLID (W)	4384+24	4397+07	1283
4"	4" SOLID (Y)	4397+07	4400+96	389
4"	4" SOLID (W)	4397+07	4400+96	389
5"	5" 30'S - 10'D	4381+76	4397+07	383
5"	5" 30'S - 10'D	4390+95	4397+07	153
5"	5" 30'S - 10'D	4397+07	4412+42	384
5"	5" 30'S - 10'D	4397+07	4412+42	384
12"	12" SOLID (W)	4389+83	4390+95	13
STAGE IB				
MOT-6				
4"	4" SOLID (Y)	2356+78	2367+00	1022
4"	4" SOLID (W)	2354+35	2367+00	1265
4"	4" SOLID (Y)	2354+35	2356+78	243
4"	6'S - 2'D (W)	2360+22	2363+22	75
4"	4" SOLID (Y)	2367+00	2382+00	1500
4"	4" SOLID (W)	2374+71	2382+00	729
4"	4" SOLID (W)	2367+00	2374+37	737
5"	5" 30'S - 10'D	2356+78	2367+00	256
5"	5" 30'S - 10'D	2356+78	2367+00	256
5"	5" 30'S - 10'D	2367+00	2382+00	375
5"	5" 30'S - 10'D	2370+28	2370+28	82
8"	8" SOLID (W)	2356+78	2360+22	344
8"	8" SOLID (W)	2356+78	2360+22	344
8"	8" SOLID (W)	2370+28	2374+71	443
8"	8" SOLID (W)	2370+28	2374+71	443
12"	12" SOLID (W)	2356+78	2360+22	137
12"	12" SOLID (W)	2370+28	2374+71	125
MOT-7				
4"	4" SOLID (Y)	4381+76	4391+37	961
4"	4" SOLID (W)	4381+76	4389+83	807
4"	4" SOLID (Y)	4384+63	4391+37	674
4"	4" SOLID (W)	4384+63	4389+83	520
5"	5" 30'S - 10'D	4381+76	4391+37	240
5"	5" 30'S - 10'D	4390+99	4391+37	10
8"	8" SOLID (W)	4389+83	4390+99	116
8"	8" SOLID (W)	4389+83	4390+99	116
12"	12" SOLID (W)	4389+83	4390+99	9
STAGE IC				
MOT-8				
4"	4" SOLID (Y)	2367+00	2382+00	1500
4"	4" SOLID (W)	2367+00	2374+76	776
4"	4" SOLID (W)	2374+60	2382+00	740
5"	5" 30'S - 10'D	2367+00	2382+00	375
5"	5" 30'S - 10'D	2367+00	2368+71	43
8"	8" SOLID (W)	2368+71	2374+60	589
8"	8" SOLID (W)	2368+71	2374+60	605
12"	12" SOLID (W)	2368+71	2374+76	707

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
MOT-9				
4"	4" SOLID (Y)	4381+76	4387+27	551
4"	4" SOLID (W)	4381+76	4387+27	551
5"	5" 30'S - 10'D	4381+76	4387+27	138
STAGE I				
MOT-4				
4"	4" SOLID (Y)	4400+96	4412+42	1146
4"	4" SOLID (W)	4400+96	4412+42	1146
MOT-10				
4"	4" SOLID (Y)	4412+42	4426+98	1456
4"	4" SOLID (W)	4412+42	4414+24	182
4"	4" SOLID (W)	4414+24	4426+98	1274
4"	6'S - 2'D (W)	4416+78	4426+98	255
4"	6'S - 2'D (W)	4426+98	4430+00	76
4"	4" SOLID (Y)	4426+98	4441+96	1498
4"	4" SOLID (W)	4426+98	4432+84	586
4"	4" SOLID (W)	4432+84	4440+60	776
4"	4" SOLID (W)	4440+60	4441+96	136
4"	6'S - 2'D (W)	4434+89	4438+07	80
5"	5" 30'S - 10'D	4412+42	4426+98	364
5"	5" 30'S - 10'D	4412+42	4426+98	364
5"	5" 30'S - 10'D	4441+96	4441+96	375
5"	5" 30'S - 10'D	4426+98	4441+96	375
8"	8" SOLID (W)	4414+24	4416+78	254
8"	8" SOLID (W)	4414+24	4416+78	254
8"	8" SOLID (W)	4432+84	4434+89	205
8"	8" SOLID (W)	4432+84	4434+89	205
8"	8" SOLID (W)	4438+07	4440+60	253
8"	8" SOLID (W)	4438+07	4440+60	253
12"	12" SOLID (W)	4414+24	4416+78	59
12"	12" SOLID (W)	4432+84	4434+89	94
12"	12" SOLID (W)	4438+07	4440+60	205
MOT-11				
4"	4" SOLID (Y)	4441+96	4457+00	1504
4"	4" SOLID (W)	4441+96	4457+00	1504
4"	6'S - 2'D (W)	4455+57	4457+00	36
4"	4" SOLID (Y)	4457+00	4471+99	1499
4"	6'S - 2'D (W)	4457+00	4458+85	46
4"	4" SOLID (W)	4457+00	4461+99	499
4"	4" SOLID (W)	4461+99	4471+99	1000
5"	5" 30'S - 10'D	4441+96	4457+00	376
5"	5" 30'S - 10'D	4441+96	4457+00	376
5"	5" 30'S - 10'D	4457+00	4471+99	375
5"	5" 30'S - 10'D	4457+00	4471+99	375
8"	8" SOLID (W)	4458+85	4461+99	314
8"	8" SOLID (W)	4458+85	4461+99	314
12"	12" SOLID (W)	4458+85	4461+99	100
MOT-12				
4"	4" SOLID (Y)	4471+99	4486+99	1500
4"	4" SOLID (W)	4471+99	4486+99	1500
4"	4" SOLID (Y)	4486+99	4502+00	1501
4"	4" SOLID (W)	4487+50	4487+50	51
4"	6'S - 2'D (W)	4488+99	4492+60	90
4"	4" SOLID (W)	4487+50	4502+00	1450
5"	5" 30'S - 10'D	4471+99	4486+99	375
5"	5" 30'S - 10'D	4471+99	4486+99	375
5"	5" 30'S - 10'D	4486+99	4502+00	375
5"	5" 30'S - 10'D	4486+99	4502+00	375
8"	8" SOLID (W)	4487+50	4488+99	149
8"	8" SOLID (W)	4487+50	4488+99	149
12"	12" SOLID (W)	4487+50	4488+99	22

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
MOT-13				
4"	4" SOLID (Y)	4502+00	4517+01	1501
4"	4" SOLID (W)	4502+00	4514+05	1205
4"	6'S - 2'D (W)	4506+05	4510+02	99
4"	4" SOLID (W)	4514+05	4517+01	296
4"	4" SOLID (Y)	4517+01	4529+76	1275
4"	4" SOLID (W)	4517+01	4529+76	1275
5"	5" 30'S - 10'D	4502+00	4517+01	375
5"	5" 30'S - 10'D	4502+00	4517+01	375
5"	5" 30'S - 10'D	4517+01	4529+76	319
5"	5" 30'S - 10'D	4517+01	4529+76	319
8"	8" SOLID (W)	4510+02	4514+05	403
8"	8" SOLID (W)	4510+02	4514+05	403
12"	12" SOLID (W)	4510+02	4514+05	102
MOT-14				
4"	SOLID (W)	4540+70.00	4542+31.00	54
4"	6'S - 2'D (W)	4543+00.00	4547+05.00	34
4"	SOLID (W)	4550+00.00	4554+05.00	135
4"	SOLID (Y)	4529+80.00	4554+05.00	808
5"	30'S - 10'D (W)	4529+80.00	4554+05.00	505
8"	@ GORES	4542+31.00	4543+00.00	92
8"	@ GORES	4547+06.00	4550+00.00	196
12"	@ GORE (DIAGONAL)	4542+31.00	4543+00.00	20
MOT-15				
4"	SOLID (W)	4554+05.00	4564+00.00	332
4"	SOLID (W)	4565+51.00	4569+83.00	144
4"	SOLID (W)	4573+88.00	4578+05.00	139
4"	SOLID (Y)	4554+05.00	4578+05.00	800
4"	6'S - 2'D (W)	4565+15.00	4571+25.00	51
5"	30'S - 10'D (W)	4554+05.00	4578+05.00	500
8"	@ GORES	4564+00.00	4565+15.00	77
8"	@ GORES	4571+25.00	4573+88.00	175
MOT-16				
4"	SOLID (W)	4578+05.00	4582+66.00	154
4"	SOLID (W)	4586+40.00	4601+00.00	487
4"	SOLID (Y)	4578+05.00	4602+05.00	800
4"	6'S - 2'D (W)	4582+66.00	4584+51.00	15
5"	30'S - 10'D (W)	4578+05.00	4602+05.00	500
8"	@ GORES	4584+51.00	4586+40.00	126
8"	@ GORES	4601+00.00	4602+05.00	70
MOT-17				
4"	SOLID (W)	4610+50.00	4616+86.00	212
4"	SOLID (W)	4621+67.00	4624+32.00	88
4"	SOLID (Y)	4602+05.00	4626+05.00	800
4"	6'S - 2'D (W)	4604+50.00	4610+50.00	50
4"	6'S - 2'D (W)	4620+17.00	4624+59.00	37
5"	30'S - 10'D (W)	4602+05.00	4626+05.00	250
5"	30'S - 10'D (W)	4602+05.00	4621+66.00	204
8"	@ GORES	4602+05.00	4604+50.00	163
8"	@ GORES	4616+86.00	4620+17.00	221
8"	@ GORES	4624+59.00	4626+05.00	97
8"	6'S - 2'D (W)	4621+66.00	4626+05.00	73
LET/SYM	LEFT TURN ONLY	4621+80.00		36
LET/SYM	LEFT TURN ONLY	4626+80.00		36
MOT-18				
4"	SOLID (W)	4626+90.00	4629+80.00	97
4"	SOLID (Y)	4626+05.00	4629+80.00	125
5"	30'S - 10'D (W)	4625+05.00	4629+80.00	49
8"	@ GORES	4626+05.00	4626+90.00	57
8"	6'S - 2'D (W)	4626+05.00	4629+80.00	63

SHEET NUMBER	LINE DESCRIPTION	STATION	TO STATION	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
STAGE II				
MOT-19				
4"	4" SOLID (Y)	4428+00	4442+00	1400
4"	6'S - 2'D (W)	4428+00	4432+00	100
4"	4" SOLID (W)	4436+98	4442+00	502
8"	8" SOLID (W)	4432+00	4436+98	498
8"	8" SOLID (W)	4432+00	4436+98	498
12"	12" SOLID (W)	4432+00	4436+98	153
12"	@ SHLDR. (DIAGONAL)	4436+98	4442+00	122
MOT-20				
4"	4" SOLID (Y)	2442+00	2457+00	1500
4"	4" SOLID (W)	2442+00	2457+00	1500
4"	4" SOLID (Y)	2457+00	2472+00	1500
4"	4" SOLID (W)	2457+00	2472+00	1500
12"	@ SHLDR. (DIAGONAL)	2442+00	2472+00	122
MOT-21				
4"	4" SOLID (Y)	2472+00	2487+00	1500
4"	4" SOLID (W)	2472+00	2487+00	1500
4"	4" SOLID (Y)	2487+00	2502+00	1500
4"	4" SOLID (W)	2487+00	2502+00	1500
4"	4" SOLID (Y)	2502+00	2517+00	1500
4"	4" SOLID (W)	2502+00	2517+00	1500
4"	4" SOLID (Y)	2517+00	2530+00	1300
4"	4" SOLID (W)	2517+00	2520+00	300
4"	6'S - 2'D (W)	4523+76	4528+00	106
12"	@ SHLDR. (DIAGONAL)	2472+00	2502+00	151
MOT-22				
8"	8" SOLID (W)	4520+00	4523+76	376
8"	8" SOLID (W)	4520+00	4523+76	376
8"	12'S - 3'D (W)	4528+00	4530+00	50
12"	12" SOLID (W)	4520+00	4523+76	122
12"	@ SHLDR. (DIAGONAL)	2502+00	2530+00	96
STAGE II				
MOT-23				
LET/SYM	LEFT TURN ONLY	4531+50.00		36
LET/SYM	LEFT TURN ONLY	4534+80.00		36
4"	SOLID (W)	4541+99.00	4626+05.00	2,802
4"	SOLID (Y)	4541+99.00	4626+05.00	2,802
8"	12'S - 3'D (W)	4529+80.00	4534+70.00	65
8"	@ GORES X 2	4534+70.00	4541+99.00	972
8"	SOLID (W)	4529+80.00	454199	813
MOT-24				
LET/SYM	LEFT TURN ONLY	4639+00.00		36
4"	SOLID (W)	4541+99.00	4642+29.00	3,343