

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90 *		COOK	556	151
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62300		* (1818, ETC, 2324.6-1P)R-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)
EX CB	44-08	1.4	12	1.00%																								1.4		
EX P	44-11	3.5	15	1.00%																								3.5	0.5	
	44-18	0.8	12	1.00%						0.8																				
	44-20	53.9	12	1.00%						53.9																			13.4	
	44-21	76.0	12	1.00%						76.0																			14.9	
EX P	44-17	2.6	12	0.20%																							2.6	0.3		
EX CB	44-17	7.6	12	1.00%																							7.6	1.2		
EX IN	44-20	7.7	12	1.00%						7.7																			1.5	
EX CB	44-21	1.8	12	1.00%						1.8																			0.0	
	45-02	0.8	12	1.00%						0.8																				
	45-04	54.5	12	1.00%						54.5																			44.1	
EX P	45-01	8.3	12	1.00%																							8.3	2.5		
EX CB	45-01	12.9	12	1.00%																							12.9	2.0		
EX CB	45-04	1.4	12	1.00%						1.4																				
	43-07	44-01	111.6	27	0.15%										111.6														130.9	
	43-03	43-07	215.0	21	0.21%								215.0																238.9	
	43-02	43-03	0.8	15	1.00%							0.8																		
	43-04	43-03	51.3	12	1.00%					51.3																			5.4	
EX CB	43-01	4.8	12	1.00%																							4.8	0.9		
EX P	43-01	3.5	12	2.00%																							3.5	0.6		
	43-06	43-07	0.8	12	1.00%					0.8																				
	43-08	43-07	52.5	12	1.00%					52.5																			5.7	
EX CB	43-05	7.4	12	1.00%																							7.4	1.2		
EX P	43-05	4.7	12	3.10%																							4.7	2.0		
	46-24	JC46-01	57.9	36	0.10%																				57.9			110.6		
	46-18	46-24	122.1	33	0.11%																								166.4	
	46-11	46-18	102.5	30	0.13%																								68.8	
	46-07	46-11	125.0	27	0.15%																								82.3	
	46-03	46-07	140.0	24	0.21%																								87.8	
	45-07	46-03	160.0	21	0.25%																								64.7	
	45-06	45-07	0.8	12	1.00%					0.8																				
	45-08	45-07	54.5	12	1.00%					54.5																			14.3	
	45-09	45-08	61.0	12	1.00%					61.0																			9.1	
EX CB	45-05	1.8	12	1.00%																							1.8	0.0		
EX CB	45-09	1.4	12	1.00%						1.4																				
	46-02	46-03	0.8	12	1.00%					0.8																				
	46-04	46-03	54.5	12	1.00%					54.5																			7.5	
EX CB	46-01	5.3	12	1.00%																							5.3	0.5		
EX P	46-01	2.6	12	2.00%																							2.6	0.2		
EX IN	46-04	4.3	12	1.00%						4.3																			0.3	
	46-06	46-07	0.8	12	1.00%					0.8																				
	46-08	46-07	54.5	12	1.00%					54.5																			6.7	
	46-23	46-08	61.0	12	1.00%					61.0																			4.6	
EX CB	46-05	1.5	12	1.00%																							1.5			
EX CB	46-08	4.4	12	1.00%						4.4																			0.4	

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S. DRAWN BY: JAM
DATE: 07/07/05 CHECKED BY: DDM

DS-36

12-4604 PM 06/28/2005