

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
066	21 (B&G) R	McHENRY	66	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

#62391

FENCE REMOVAL

STA TO STA	FOOT
104+51 TO 106+32 LT	214
TOTAL	214

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2

STA	EACH
STAGE I	
106+75 RT	1
106+75 LT	1
107+25 RT	1
109+25 RT	1
109+75 RT	1
109+75 LT	1
110+25 RT	1
110+25 LT	1
TOTAL	8

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 2

STA	EACH
STAGE II	
98+60 LT	1
104+20 LT	1
105+00 RT	1
107+45 RT	1
107+80 RT	1
113+40 RT	1
113+60 RT	1
115+00 RT	1
TOTAL	8

TURF REINFORCEMENT MAT

STA TO STA	SQ YD
107+15 TO 107+48 RT	75
TOTAL	75

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C," N50

STA	TONS
97+50 RT	6
102+62 RT	6
104+50 LT	6
104+95 RT	6
107+66 RT	5
108+62 LT	6
111+82 LT	9
113+50 RT	6
113+74 LT	21
116+41 RT	7
TOTAL	78

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D," N50

STA TO STA	TONS
104+00 TO 115+10	250
TOTAL	250

LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50

STA TO STA	TONS
104+00 TO 115+10	248
106+87.25 TO 107+12.75 RT	1
106+87.25 TO 107+12.75 LT	1
109+83.4 TO 110+16.6 RT	1
109+83.4 TO 110+16.6 LT	1
TOTAL	252

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 3 SPECIAL

STA	EACH
STAGE I	
106+75, 10 RT	1
106+75, 36 RT	1
107+25, 36 RT	1
109+25, 10 RT	1
109+75, 10 RT	1
109+75, 36 RT	1
110+25, 10 RT	1
110+25, 36 RT	1
STAGE II	
106+75, 5 RT	1
107+25, 5 RT	1
109+75, 5 RT	1
110+25, 5 RT	1
TOTAL	12

CONSTRUCTION LAYOUT

LOCATION	LUMP SUM
PROJECT	1

TEMPORARY INFORMATION SIGNING

LOCATION	SQ FT
2 UNDISTRIBUTED	51.4
TOTAL	51.4

TEMPORARY PAVEMENT

LOCATION	SQ YD
STAGE I DETOUR	4063
STAGE II DETOUR	792
TOTAL	4855

TEMPORARY ACCESS (PRIVATE ENTRANCE)

STA	EACH
102+62 RT	1
108+62 LT	1
116+41 RT	1
TOTAL	3

TEMPORARY ACCESS (COMMERCIAL ENTRANCE)

STA	EACH
107+66 RT	1
110+60 LT	1
113+74 LT	1
TOTAL	3

TEMPORARY ACCESS (FIELD ENTRANCE)

STA	EACH
104+66	1
104+98	1
TOTAL	2

BITUMINOUS BASE COURSE SUPERPAVE 6"

STA	SQ YD
102+62 RT	52
104+50 LT	52
104+95 RT	50
108+62 LT	50
113+50 RT	50
116+41 RT	61
TOTAL	315

BITUMINOUS BASE COURSE SUPERPAVE 8"

STA	SQ YD
107+66 RT	76
111+82 LT	80
113+74 LT	213
TOTAL	369

TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED

STA	EACH
106+00 37' LT	1
106+20 37' LT	1
106+40 37' LT	1
106+34 36' RT	1
106+54 36' RT	1
110+68 34' RT	1
110+88 34' RT	1
111+08 34' RT	1
TOTAL	8

TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED

STA	EACH
104+46 32' RT	1
104+66 32' RT	1
105+26 32' RT	1
107+46 35' LT	1
107+66 35' LT	1
107+86 35' LT	1
108+06 35' LT	1
109+70 32' LT	1
112+31 38' LT	1
112+51 38' LT	1
112+71 38' LT	1
112+91 38' LT	1
TOTAL	12

SHRUB, VIBURNUM PRUNIFOLIUM (BLACKHAWK VIBURNUM), 6' HEIGHT, BALLED AND BURLAPED

STA	EACH
104+22 38' LT	1
104+88 38' LT	1
105+08 38' LT	1
108+28 38' LT	1
109+16 40' LT	1
109+36 40' LT	1
111+00 48' LT	1
111+20 48' LT	1
114+54 37' RT	1
114+62 32' LT	1
114+74 37' RT	1
114+82 32' LT	1
TOTAL	12

RELOCATE TEMPORARY CONCRETE BARRIER

STA TO STA	FOOT
STAGE I TO STAGE II	400
TOTAL	400

THERMOPLASTIC PAVEMENT MARKING-LINE 4"

STA TO STA	FOOT
97+00 TO 122+10 SINGLE YELLOW DASHED	628
97+00 TO 103+45 SINGLE YELLOW SOLID	645
97+00 TO 122+10 WHITE EDGELINE (2)	5020
TOTAL	6293

RAISED REFLECTIVE PAVEMENT MARKER

STA TO STA	EACH
97+00 TO 122+10	32
TOTAL	32

BARRIER WALL MARKERS, TYPE C

LOCATION	EACH
STAGE I	32
STAGE II	120
TOTAL	152

PAVEMENT MARKING REMOVAL

STA TO STA	SQ FT
97+00 TO 104+00	467
118+10 TO 122+10	467
97+00 TO 122+10 RT	837
TOTAL	1771

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STA TO STA	EACH
97+00 TO 104+00	9
115+10 TO 122+10	9
TOTAL	18

3287Schedule1.e. DGN



REVISIONS	
NAME	DATE
KWN	4-11-05

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14 OVER LAWRENCE CREEK
SCHEDULE OF QUANTITIES

DRAWN BY CLG
CHECKED BY JJD

DATE: 2-17-05