

62912

F.A.P. RTE.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	1453	2005-0058	COOK/DUPAGE	14	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES			URBAN X080-2A		CONSTRUCTION TYPE CODE SFTY-2A			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOC. 1 COOK 016-0525	LOC. 2 DUPAGE 022-0084			
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	110.6	10.6	100			
50102400	CONCRETE REMOVAL	CU YD	22.7	5.9	16.8			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.2	13.5	18.7			
50300300	PROTECTIVE COAT	SQ YD	117.3	44.7	72.6			
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	569	569				
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	2169		2169			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1260		1260			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3560	1410	2150			
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	78	78				
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	356.8	51.8	305			
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	1487	268	1219			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	0.5	0.5			
67100100	MOBILIZATION	L SUM	1	0.5	0.5			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	80		80			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	760	120	640			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	760	120	640			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	100	100				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1640	200	1440			
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	2796	575	2221			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	48	48			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", NSO	TON	41.8	7.5	34.3			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	30	2	28			

SUMMARY OF QUANTITIES			URBAN X080-2A		CONSTRUCTION TYPE CODE SFTY-2A			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOC. 1 COOK 016-0525	LOC. 2 DUPAGE 022-0084			
Δ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2	2			
Δ Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	1	1			

Δ SFTY-3N  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

4/15/2005 11:00:00 AM