

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(46-2HB)I	KANKAKEE	10	2
STA. 1224+55.93 TO STA. 1226+60.23				

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

The cost of any saw cuts made to complete the work as described in plan details, unless otherwise noted shall not be paid for separately but shall be included in the various pay items involved.

The finished earthwork shall have a vegetation sustaining soil covering the top four inches (4") in areas to be seeded or sodded. The vegetation sustaining soil required shall be measured and paid for in accordance with Section 205 of the Standard Specifications.

For stabilization, all Type II barricades shall require a minimum of two sand bags per barricade. For stabilization, all Type III barricades shall require a minimum of four sand bags per barricade.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.

All elevations referring to U.S.G.S. mean sea level datum.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

New Reinforcement bars shall be Epoxy Coated.

Reinforcement bars that are to remain in place which are damaged during concrete removal operations shall be repaired or replaced using approved bar splicer or anchorage system. Cost included with "Concrete Removal".

Reinforcement bars shall conform to the requirements of AASHTO M 31 or M322 Grade 60.

DATE: May 18, 2005

PREPARED BY: *Bruce A. Hucker*
DISTRICT OPERATIONS ENGINEER

EXAMINED BY: *Robert K. [Signature]*
DISTRICT CONSTRUCTION ENGINEER

Steven B. [Signature]
ACTING DISTRICT STUDIES & PLANS ENGINEER

Kenneth L. [Signature]
DISTRICT MATERIALS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
GENERAL NOTES
F.A.I. ROUTE 57 SECTION (46-2HB)I
KANKAKEE COUNTY
S.N. 046-0088
STA. 225 + 59.91
DATE 04/12/05
DRAWN BY RLW
CHECKED BY

DATE: 04/12/05
FILE NAME: c:/projects/cmain06/cm304/details.dgn