

PAVEMENT MARKING SCHEDULE							
STATION	TYPE	THERMOPLASTIC PAVEMENT MARKING - LINE 5"		THERMOPLASTIC PAVEMENT MARKING LINE 12" - YELLOW	PREFORMED PLASTIC PAV'T MARKING LETTERS & SYMBOLS	PREFORMED PLASTIC PAV'T MARKING LINE 5" - WHITE	PREFORMED PLASTIC PAV'T MARKING LINE 6" - WHITE
		WHITE	YELLOW				
STA. 467+45.39 TO 513+53.39	EDGE LINE	8,764 FT					
STA. 467+45.39 TO 513+53.39	SKIP-DASH		1,290 FT				
STA. 467+45.39 TO 513+53.39	MEDIAN LINE		3,771 FT				
STA. 467+45.39 TO 513+53.39	BI-DIRECTIONAL TURN LANE		5,161 FT				
STA. 467+45.39 TO 513+53.39	TURN LANE		1,342 FT				
STA. 467+45.39 TO 513+53.39	GORE LINE			188 FT			
STA. 467+45.39 TO 513+53.39	TURN ARROW				702 SQ FT		
STA. 467+45.39 TO 513+53.39	SKIP-DASH					319 FT	
STA. 467+45.39 TO 513+53.39	TURN LANE						707 FT
<b>TOTALS</b>		8,764 FT	11,564 FT	188 FT	702 SQ FT	319 FT	707 FT

NOTES:

1. STATIONS ARE APPROXIMATE.
2. SEE SHEETS 16-27 FOR PAVEMENT MARKING LOCATIONS.

MIXTURE REQUIREMENTS	
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT	
MIXTURE USE(S):	POLYMERIZED BIT.CONC. SURF. CRSE., SUPER, MIX "D", N90
AC/PG	SBS PG 70-22
RAP %: (MAX)	0%
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 90
MIXTURE COMP:	IL 9.5 OR 12.5
FRICTION AGG:	MIX "D"

SCHEDULES  
FAU 8041 (DIRKSEN PKWY)  
SECTION 28RS-7  
SANGAMON COUNTY