

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1771	25RS-7	LOGAN	8	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LOCATION OF WORK				ROADWAY	SN 054-2000 STA 638+04.5 TO STA 638+31.5
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	SFTY-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.5	9.4	0.1
40600300	AGGREGATE (PRIME COAT)	TON	50	49.8	0.2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	129	129	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	10	10	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	25,079	24,998	81
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH	SQ YD	25	25	
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	275	275	
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	75	75	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	627	625	2
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,477	2,469	8
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	18,581	18,520	61
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	275	274	1
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	18,581	18,520	61
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	2,100	2,093	7
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	1,050	1,047	3

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAS 1771 (OLD US 66)  
SECTION 25RS-7  
LOGAN COUNTY

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY