

steffemk  
 3/29/2005  
 c:\projects\74073d\05404pa.dgn  
 QTY SCH

CONTRACT NO. 74073

|                     |          |                  |              |           |
|---------------------|----------|------------------|--------------|-----------|
| F.A.P. RTE.         | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
| 726                 |          | JEFFERSON        | 10           | 4         |
| STA.                |          | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT |              |           |

• D-7 JOINT REPAIRS 2005-1

BRIDGE REPAIR SCHEDULE

|              | LENGTH       | CONCRETE REMOVAL |             | REINFORCEMENT BARS, EPOXY COATED | BAR SPLICERS | NEOPRENE EXPANSION JOINT 2 1/2" | NEOPRENE EXPANSION JOINT 4" |
|--------------|--------------|------------------|-------------|----------------------------------|--------------|---------------------------------|-----------------------------|
| 041-0096     | FEET         | CU FT            | CU FT       | POUND                            | EACH         | FEET                            | FEET                        |
| Stage I      | 646.7        | 17.07            | 17.14       | 3148                             | 40           | 34                              | 17                          |
| Stage II     |              | 17.07            | 17.14       | 3148                             |              | 34                              | 17                          |
| <b>TOTAL</b> | <b>646.7</b> | <b>34.1</b>      | <b>34.3</b> | <b>6296</b>                      | <b>40</b>    | <b>68</b>                       | <b>34</b>                   |

PAVEMENT MARKING SCHEDULE

|              | PAINT PAVEMENT MARKING - LINE 4" | PAVEMENT MARKING REMOVAL | TEMPORARY PAVEMENT MARKING - LINE 4" | SHORT TERM PAVEMENT MARKING | WORK ZONE PAVEMENT MARKING REMOVAL | RAISED REFLECTOR PAVEMENT MARKER, REFLECTOR REMOVAL | REPLACEMENT REFLECTOR |
|--------------|----------------------------------|--------------------------|--------------------------------------|-----------------------------|------------------------------------|-----------------------------------------------------|-----------------------|
| 041-0096     | FEET                             | SQ FT                    | FEET                                 | FEET                        | SQ FT                              | EACH                                                | EACH                  |
| <b>TOTAL</b> | <b>1942</b>                      | <b>637</b>               | <b>5940</b>                          | <b>57</b>                   | <b>1386</b>                        | <b>8</b>                                            | <b>8</b>              |

PLOT DATE = 3/29/2005  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**QUANTITY SCHEDULES**

SCALE: VERT. HORIZ.  
 DATE

DRAWN BY  
 CHECKED BY