

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
325	113RS-2	JERSEY	8	2
STA _____		TO STA _____		
CONTRACT NUMBER:			76937	

**GENERAL NOTES**

1. THE STANDARDS AND REVISIONS NUMBERS LISTED APPLY TO THIS PROJECT.
2. IF ANY SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR RESURFACED OVER. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCE THEIR LOCATION.
3. THE THICKNESS OF BITUMINOUS MIXTURES SHOWN IN THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
4. AN ESTIMATED 2,870 TONS OF BITUMINOUS SURFACE WILL BE REMOVED.
5. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT.

MIXTURE REQUIREMENTS	
MIXTURE USE	SURFACE
ACPG	PG 64-22
RAP% (MAX)	15%
DESIGN AIR VOIDS	4.0% @ Ndes = 50
MIX COMPOSITION (GRADATION MIXTURE)	
FRICITION AGG	MIXTURE "C"

6. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
7. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
8. UTILITY CONFLICTS ARE NOT ANTICIPATED ON THIS CONTRACT. SHOULD THIS PROVE TO BE OTHERWISE DURING ANY OF THE REQUIRED OPERATIONS. THE ENGINEER IS TO BE NOTIFIED AT THE TIME OF THE OCCURRENCE. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM THIS OCCURRENCE. THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.) SYSTEM NUMBER IS (800-892-0123).
  - \* AMEREN-CIPS
  - \* FRONTIER COMMUNICATIONS COMPANY
  - \* JERSEY COUNTY RURAL WATER COMPANY
9. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT ENTRANCES AND SIDE STREETS WHERE WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGN SHALL BE FLORESCENT ORANGE. THIS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION.
10. SHORT-TERM PAVEMENT MARKINGS SHALL BE APPLIED TO THE MILLED, PRIMED, AND FINAL BITUMINOUS SURFACE. A QUANTITY FOR TEMPORARY PAVEMENT MARKING EQUAL TO THE AMOUNT OF PERMANENT PAVEMENT MARKING HAS BEEN ADDED TO THE PLANS.
11. ALL TEMPORARY PAVEMENT MARKING WILL BE PLACED IN SUCH A MANNER SO AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

**INDEX OF SHEETS**

1. COVER SHEET
2. INDEX OF SHEETS, HIGHWAY STANDARDS, MIXTURE REQUIREMENTS, GENERAL NOTES, AND COMMITMENTS
3. SUMMARY OF QUANTITIES
- 4.-5. TYPICAL SECTIONS
6. SCHEDULES OF QUANTITIES
7. LOCATION MAP
8. PLAN DETAILS

**LIST OF STANDARDS**

- 000001-04
- 442201-01
- 701011-01
- 701301-02
- 701306-01
- 701311-02
- 701336-04
- 702001-05
- 780001-01
- 781001-02

**COMMITMENT**

NONE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**INDEX OF SHEETS,  
STANDARDS, GENERAL NOTES**  
FAP ROUTE 325 (IL 16)  
SECTION 113RS-2  
JERSEY COUNTY

DRAWN BY:

PLOT DATE: \*DATE-TIME\*

DATE	BY	REVISIONS	PLANNED	DESIGNED	CHECKED	DATE

STATES  
\*DATE-TIME\*  
\*DATE-TIME\*  
\*DATE-TIME\*