ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
325	113RS-2	JERSEY	8	3
STA. _____		TO STA. _____		
CONTRACT NUMBER: 76937				

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: RURAL 1000 100% STATE	-------	-------
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	33		
40600300	AGGREGATE (PRIME COAT)	TON	154	154		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	342	342		
40600990	TEMPORARY RAMP	SQ YD	139	139		
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	102444	102444		
44200274	PAVEMENT PATCHING, TYPE I	SQ YD	6.7	6.7		
44200276	PAVEMENT PATCHING, TYPE II	SQ YD	86.1	86.1		
44200278	PAVEMENT PATCHING, TYPE III	SQ YD	17.8	17.8		
44200280	PAVEMENT PATCHING, TYPE IV	SQ YD	86.7	86.7		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1402	1402		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6828	6828		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	96162	96162		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1175	1175		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	96162	96162		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	469	469		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	469	469		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	8606	8606		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: -------	-------	-------

*SPECIALTY ITEMS

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
REFERENCE = #REF#