

THERMOPLASTIC PAVEMENT MARKINGS

LOCATION			SKIP DASH YELLOW 4 IN (FT)	YELLOW 4 IN (FT)	WHITE 4 IN (FT)	EAST BOUND	WEST BOUND		
MILE STA	TO	MILE STA							
15.59	TO	15.61		211.2	211.2	NO PASSING	NO PASSING		
15.61	TO	15.72	145.2	580.8	1161.6	PASSING	NO PASSING		
15.72	TO	15.79	92.4		739.2	PASSING	PASSING		
15.79	TO	15.93	184.8	739.2	1478.4	NO PASSING	PASSING		
15.93	TO	16.01	105.6		844.8	PASSING	PASSING		
16.01	TO	16.06	BRIDGE OMISSION						
16.06	TO	16.77	937.2		7497.6	PASSING	PASSING		
16.77	TO	16.92	198	792	1584	PASSING	NO PASSING		
16.92	TO	16.98	79.2		633.6	PASSING	PASSING		
16.98	TO	17.16	237.6	950.4	1900.8	PASSING	NO PASSING		
17.16	TO	17.35	250.8		2006.4	PASSING	PASSING		
17.35	TO	17.39	BRIDGE OMISSION						
17.39	TO	17.57	237.6	950.4	1900.8	NO PASSING	PASSING		
17.57	TO	17.59		211.2	211.2	NO PASSING	NO PASSING		
17.59	TO	17.82	303.6	1214.4	2428.8	PASSING	NO PASSING		
17.82	TO	18.84	1346.4		10771.2	PASSING	PASSING		
18.84	TO	18.94	132	528	1056	NO PASSING	PASSING		
18.94	TO	19.31	488.4		3907.2	PASSING	PASSING		
19.31	TO	19.4	118.8	475.2	950.4	NO PASSING	PASSING		
19.4	TO	19.55	198		1584	PASSING	PASSING		
19.55	TO	19.63	105.6	422.4	844.8	PASSING	NO PASSING		
19.63	TO	19.65		211.2	211.2	NO PASSING	NO PASSING		
19.65	TO	19.76	145.2	580.8	1161.6	NO PASSING	PASSING		
19.76	TO	19.84	105.6		844.8	PASSING	PASSING		
19.84	TO	19.97	171.6	686.4	1372.8	PASSING	NO PASSING		
19.97	TO	20.15	237.6		1900.8	PASSING	PASSING		
20.15	TO	20.26	145.2	580.8	1161.6	NO PASSING	PASSING		
20.26	TO	20.36	132		1056	PASSING	PASSING		
20.36	TO	20.47	145.2	580.8	1161.6	PASSING	NO PASSING		
20.47	TO	21.7	1623.6		12988.8	PASSING	PASSING		
21.7	TO	21.8	132	528	1056	NO PASSING	PASSING		
21.8	TO	21.97	224.4		1795.2	PASSING	PASSING		
21.97	TO	22.07	132	528	1056	PASSING	NO PASSING		
22.07	TO	22.5	567.6		4540.8	PASSING	PASSING		
22.5	TO	22.69	250.8	1003.2	2006.4	NO PASSING	PASSING		
22.69	TO	22.79	132		1056	PASSING	PASSING		
TOTAL:			9306	11774.4	75081.6				
			96162						

RAISED REFLECTIVE PAVEMENT MARKERS				
LOCATION			DOUBLE AMBER	REMOVAL
MILE STA	TO	MILE STA		
15.59	TO	16.01	28	28
16.01	TO	16.06	BRIDGE OMISSION	
16.06	TO	17.35	85	85
17.35	TO	17.39	BRIDGE OMISSION	
17.39	TO	22.79	356	356
TOTAL:			469	469

PAVEMENT PATCHING

PATCH LOCATION		PATCH SIZE	PATCH TYPE			
MILE STA.	LANES		I	II	III	IV
17.79	WB	6X20		13.3		
	WB	6X30				20
	WB	6X15		10		
18.69	WB	12X15				20
18.89	WB	6X15		10		
19.19	EB	6X6	4			
19.59	WB	12X8		10.7		
19.99	WB	6X4	2.7			
20.39	WB	12X15				20
20.79	WB	12X8		10.7		
22.19	WB	12X8		10.7		
	WB	40X4			17.8	
22.79	WB	12X20				26.7
	EB	12X8		10.7		
EB	6X15			10		
SUB TOTALS:			6.7	86.1	17.8	86.7

RESURFACING SCHEDULE

MILE STA	TO	MILE STA	BIT. CONC. SURF. CSE. MIX C, N50 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	BIT. SURF. REMOVAL 1/2" SQ. YDS.	AGGREGATE SHOULDER TONS
15.59	TO	16.01	538.6	2.2	9.6	6406.9	83
BRIDGE OMISSION							
16.06	TO	17.35	1652.9	6.3	29.6	19676.8	255
BRIDGE OMISSION							
17.39	TO	17.67	358.8	1.4	6.4	4270.7	55
17.67	TO	22.79	6055.7	22.7	108.4	72089.6	1009
TOTAL:			8606	32.6	154	102444	1402

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 325 (IL 16)
SECTION 113RS-2
JERSEY COUNTY

REVISIONS	
NAME	DATE

DRAWN BY:

PLOT DATE: *DATE-TIME*

PLAN
DATE: _____
BY: _____
CHECKED BY: _____
DATE: _____
SCALE: _____

QUANTITIES
DATE-TIME
DATE-TIME
DATE-TIME