CONTRACT NO. 76966

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	**	***	25	4
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

** DIST 8 ITS 2006-1

*** MADISON & ST. CLAIR

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION CODE SFTY Y032-1F LOCATION 557005.9A.27D	LOCATION 557007.0A.28D	LOCATION 557008.0A.29D	LOCATION 557009.1A.30D	LOCATION 025524.7A.39C	TMC
X0325073	MODIFY EXISTING CONTROLLER CABINET TYPE B	EACH	1					1	
X0325074	TRAFFIC DATA COLLECTION SYSTEM	L SUM	1						1
XX005229	VIDEO TRANSMISSION SYSTEM	L SUM	1						1
X0325075	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT	FOOT	60		30	30			
X8730050	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 2 3/C COPPER	FOOT	1807			1807			
X0325077	FIBER OPTIC UTILITY MARKER	EACH	110	22	20	22	16	12	18
X0325076	WIDE AREA NETWORK	L SUM	1						1
X0322227	CLOSED CIRCUIT TELEVISION CAMERA SYSTEM	EACH	1			1			
X0322343	LOCATE EXISTING DRAINAGE STRUCTURE	EACH	20	4	4	4	3	5	
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	25637	6120	5300	5310	4005	3252	1650
X0324592	2070 CONTROLLER	EACH	4	1	1	1	1		
X8360100	LIGHT POLE FOUNDATION, 28" DIAMETER	FOOT	7.5			7.5			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1				
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	4		2	2			

Rev.

PLOT DATE = 5/25/2005
FILE NAME = c:\projects\ed01202\electrical\tsp\ed01202a.dgn
PLOT SCALE = 99.9998 ' / IN.
REFERENCE = REF