

CONTRACT NO: 83763

**ROADWAY SCHEDULE**


LOCATION	BRIDGE APPROACH PAVEMENT	FLEXIBLE PAVEMENT CONNECTOR	PCC DRIVEWAY PAVEMENT	SUB-BASE GRAN. MATL. TYPE A	SUB-BASE GRAN. MATL. TYPE B	BITUMINOUS SURF. CSE. SUPERPAVE MIX C N50	BITUMINOUS SURF. CSE. SUPERPAVE MIX D N70	BITUMINOUS BINDER CSE. SUPERPAVE IL-19.0 N50	LEVELING BINDER M M SUPERPAVE N70	AGGREGATE SURFACE COURSE. TYPE A	AGGREGATE SHOULDER. TYPE A (SPECIAL)	AGGREGATE BASE CSE. TYPE A (SPECIAL)	BIT. SURFACE REMOVAL BUTT-JOINT	BIT. BASE CSE. SUPERPAVE	BIT. BASE CSE. SUPERPAVE	BIT. BASE CSE. SUPERPAVE	INCIDTL. BIT. SURFACING SUPERPAVE N50	BIT. MATERIAL PRIME COAT	AGGREGATE PRIME COAT	STRIP REFLECTIVE CRACK CONTROL	PAVED SHOULDER REMOVAL	PAVEMENT REMOVAL	TEMPORARY RAMP
	SQ YD	SQ YD	SQ YD	4"	4"	TON	TON	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	GAL	TON	FOOT	SQ YD	SQ YD	SQ YD
PRESTAGE 1																							
STA. 13+46.02 TO STA. 17+65					185									153							185		
STA. 17+65 TO STA. 20+73.63					173									142							173		
STAGE 1																							
STA. 13+46.02 TO STA. 17+65	58.30	12.30	26.70	64.85	111	15	4	14	52		8	50	230	83	214			161		325	235	81	24
STA. 17+65 TO STA. 20+73.63	58.30	11.80	26.30	64.10	96	23	5	20	26		12	73	278	72	225			182		215	226	69	45
STAGE 2																							
STA. 13+46.02 TO STA. 17+65	78.30	16.30		85.70				120	14							187		101	2.02	325	111	165	13
STA. 17+65 TO STA. 20+73.63	78.30	15.70		83.40				87	6							168		67	1.34	215	143	140	13
ENTRANCES										20.4										8.3	0.7		
TOTAL	273.2	56.10	53.00	298.05	565	38	216	34	98	20.40	20	123	508	450	439	355	8.30	511.70	3.36	1080	1073	455	95
TOTAL USE	274	56	53	298	565	38	216	34	98	20	20	123	508	450	439	355	8	512	4	1080	1073	455	95

**ENTRANCE SCHEDULE**

LOCATION	Type	Existing Surface	Existing Width	Proposed Width	Proposed Surface	Radius	Incidental Bituminous Surfacing 2.5" TON	Aggregate Surface Course Type A 6" TON	BIT. MATL. PRIME COAT GAL.
MILLBURN RD.			FOOT	FOOT		FOOT			
LT. STA. 14+53	PE	BIT	16.00	16.00	BIT	12	5.14	12.66	0.42
RT. STA. 20+11	PE	BIT	16.00	16.00	BIT	12	3.12	7.70	0.26
TOTAL							8.27	20.36	0.68
TOTAL USE									

**RIPRAP SCHEDULE**

LOCATION	WIDTH	LENGTH	STONE RIPRAP CLASS A4	FILTER FABRIC
	FEET	FEET	TONS	SQ YD
MILLBURN RD.				
RT. STA. 18+45	9	5	4	5
RT. STA. 18+90	6	6	3	4
BRIDGE			676	843
TOTAL			683	852
USE			683	852

 Account Number 12-07-0043-1 Date: 06/28/04 DESIGNED: S.W.M. CHECKED: L.F.S. DRAWN: W.J.S.	Rice, Berry and Associates A Division of Hampton, Lenzini and Renwick, Inc. Civil & Structural Engineers 801 S. Durkin Drive Springfield, Illinois 62704 217-546-3400 P.O. Box 1036 DuQuoin, Illinois 62832 618-190-4631	<p><b>SCHEDULE OF QUANTITIES</b></p> <p>SECTION 99-00076-11-BR</p> <p>C.H. 14 / MILLBURN ROAD</p> <p>LAKE COUNTY</p>
--	--	--