

SUMMARY OF QUANTITIES

F.A.P. ROUTE	COUNTY SECTION	COUNTY	TOTAL SHEETS
336	99-00243-00-PV	KANE	268
CONTRACT NO. 83792			3C
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS PROJECT F-0336(008)			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE												
				J000-2A ROADWAY STA	J000-2A ROADWAY STU	Y003-TEA LANDSCAPING STU	Y003-TEA LANDSCAPING CITY NON-PART.	Y030-1E LIGHTING STU	Y030-1E LIGHTING CITY NON-PART.	Y031-1F SIGNALS DEAN STREET STU (1)	Y031-1F SIGNALS IL ROUTE 64 STU (2)	Y031-1F SIGNALS INTERCONNECT STU (3)	Y045-BTPW,TEA UNDERPASS STU	Y060 SANITARY CITY NON-PART.(1)	Y060 WATER MAIN CITY NON-PART.(2)	
55036900	STORM SEWERS, TYPE 3, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 53, RISE 34	FOOT	140	140												
55100500	STORM SEWER REMOVAL 12"	FOOT	2,847	1,656	1,191											
55100700	STORM SEWER REMOVAL 15"	FOOT	1,368	759	609											
55100900	STORM SEWER REMOVAL 18"	FOOT	1,876	1,466	410											
55101200	STORM SEWER REMOVAL 24"	FOOT	439	95	344											
55101300	STORM SEWER REMOVAL 27"	FOOT	426	426												
55101400	STORM SEWER REMOVAL 30"	FOOT	520	291	229											
55101600	STORM SEWER REMOVAL 36"	FOOT	1,759		1,759											
55101800	STORM SEWER REMOVAL 42"	FOOT	525	390	135											
55102100	STORM SEWER REMOVAL 60"	FOOT	26	26												
* 56102900	DUCTILE IRON WATER MAIN 4"	FOOT	40													40
* 56103000	DUCTILE IRON WATER MAIN 6"	FOOT	703													703
* 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	40													40
* 56103200	DUCTILE IRON WATER MAIN 10"	FOOT	999													999
* 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	5,502													5,502
* 56103400	DUCTILE IRON WATER MAIN 16"	FOOT	2,237													2,237
* 56104800	WATER VALVES 4"	EACH	2													2
* 56104900	WATER VALVES 6"	EACH	6													6
* 56105000	WATER VALVES 8"	EACH	2													2
* 56105100	WATER VALVES 10"	EACH	5													5
* 56105200	WATER VALVES 12"	EACH	20													20
* 56105300	WATER VALVES 16"	EACH	6													6
* 56106600	ADJUSTING WATER MAIN 12"	FOOT	30	30												
* 56108800	TAPPING VALVES AND SLEEVES 6"	EACH	1													1
* 56109100	TAPPING VALVES AND SLEEVES 12"	EACH	1													1
* 56200300	WATER SERVICE LINE 1"	FOOT	305													305
* 56200500	WATER SERVICE LINE 1 1/2"	FOOT	20													20
* 56201400	CORPORATION STOPS 1"	EACH	9													9
* 56201600	CORPORATION STOPS 1 1/2"	EACH	1													1
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1												
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	1	1											
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	13													13
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	31													31
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	265										265			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1										1			
60107600	PIPE UNDERDRAINS 4"	FOOT	5,929	5,532	397											
60107700	PIPE UNDERDRAINS 6"	FOOT	253										253			
60202405	CATCH BASINS, TYPE A, 4'-DIAMETER	EACH	176	130	46											
60205605	CATCH BASINS, TYPE A, 5'-DIAMETER	EACH	23	20	3											
60206705	CATCH BASINS, TYPE B	EACH	1	1												
60220200	MANHOLES, TYPE A, 4'-DIAMETER	EACH	27	17	10											
60222900	MANHOLES, TYPE A, 5'-DIAMETER	EACH	43	32	11											
60224075	MANHOLES, TYPE A, 6'-DIAMETER	EACH	2	2												
60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11												11	
60238800	INLETS, TYPE A	EACH	2	1	1											
60249110	VALVE VAULTS, 4'-DIAMETER	EACH	11													11
60249120	VALVE VAULTS, 5'-DIAMETER	EACH	32													32
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1												
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6												
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3												
60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1												
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1												
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	16	11	5											
60266500	VALVE VAULTS TO BE REMOVED	EACH	17	15	2											
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1		1											
60266910	VALVE BOXES TO BE REMOVED	EACH	8	2	6											

* SPECIALTY ITEM