

SUMMARY OF QUANTITIES

F.A.P. ROUTE	COUNTY SECTION	COUNTY	TOTAL SHEETS
336	99-00243-00-PV	KANE	268
CONTRACT NO.			3F
83782			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS		PROJECT F-0336(008)	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				J000-2A ROADWAY STA	J000-2A ROADWAY STU	Y003-TEA LANDSCAPING STU	Y003-TEA LANDSCAPING CITY NON-PART.	Y030-1E LIGHTING STU	Y030-1E LIGHTING CITY NON-PART.	Y031-1F SIGNALS DEAN STREET STU (1)	Y031-1F SIGNALS IL ROUTE 64 STU (2)	Y031-1F SIGNALS INTERCONNECT STU (3)	Y045-BTPW,TEA UNDERPASS STU	Y060 SANITARY CITY NON-PART.(1)	Y060 WATER MAIN CITY NON-PART.(2)		
* X0301828	ENGINEERED BARRIER	SQ YD	434	217	217												
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	8	7	1												
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	11	6	5												
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	540	200	340												
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	700	700													
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	7,600									7,600					
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,422											1,422			
X0632001	CLEAR PROTECTIVE COATING FOR CONCRETE	SQ FT	4,835											4,835			
X0712400	TEMPORARY PAVEMENT	SQ YD	4,000	3,000	1,000												
X0840000	SANITARY SEWER REMOVAL 8"	FOOT	543														543
X3550215	BITUMINOUS BASE COURSE SUPERPAVE 5 3/4"	SQ YD	1,478	1,478													
X3550515	BITUMINOUS BASE COURSE SUPERPAVE 8 3/4"	SQ YD	8,989		8,989												
X3550615	BITUMINOUS BASE COURSE SUPERPAVE 9 3/4"	SQ YD	6,690	6,690													
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	474	474													
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	5,529	3,214	2,315												
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	200	200													
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	2,123	905	1,218												
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	601	318	283												
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	180	120	60												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	20	10	10												
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	72	36	36												
* X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ FT	1,807	1,286	521												
* X7800510	POLYUREA PAVEMENT MARKING SPECIAL - LINE 4"	FOOT	28,430	21,653	6,777												
* X7800530	POLYUREA PAVEMENT MARKING SPECIAL - LINE 6"	FOOT	7,720	5,678	2,042												
* X7800540	POLYUREA PAVEMENT MARKING SPECIAL - LINE 8"	FOOT	475	475													
* X7800550	POLYUREA PAVEMENT MARKING SPECIAL - LINE 12"	FOOT	1,883	1,828	55												
* X7800580	POLYUREA PAVEMENT MARKING SPECIAL - LINE 24"	FOOT	688	555	133												
* X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2														
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	7,962									7,962					
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,798							832	966						
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,934							654	1,280						
* X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12							2	10						
* X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2								2						
* X8801460	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	8							6	2						
* X8801437	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	6							2	4						
* X8801447	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2							2							
* X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	14							6	8						
* X8810630	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED	EACH	2							2							
* XX000739	CURB STOP & BOX 1 INCH	EACH	9														9
* XX002856	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1										1				
* XX002956	PARTIAL BUILDING REMOVAL AND RECONSTRUCTION	L SUM	1		1												
XX003503	FLARED END SECTION REMOVAL	EACH	21		21												
* XX003553	VIDEO TRANSMISSION SYSTEM	EACH	1										1				
* XX003651	ELECTRIC CABLE IN CONDUIT, COAXIAL	FOOT	85									85					
* XX003885	IRRIGATION SYSTEM	L SUM	1					1									
* XX004558	RAILROAD FLAGMEN	UNIT	50,000		50,000												
XX004852	BITUMINOUS DRIVEWAY PAVEMENT, SUPERPAVE	SQ YD	2,988		2,988												
XX005078	CATCH BASINS, TYPE C, 2' DIAMETER	EACH	32		32												
XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	1		1												
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	4,000		4,000												
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	60,342		60,342												
Z0002600	BAR SPLICERS	EACH	298										298				
* Z0007601	BUILDING REMOVAL NO. 1	L SUM	1		1												
* Z0007602	BUILDING REMOVAL NO. 2	L SUM	1		1												
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1												
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1,000		1,000												

\* SPECIALTY ITEM