

SUMMARY OF QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
AR156511	DITCH CHECK	EACH	16
AR156520	INLET PROTECTION	EACH	9
AR156521	HEADWALL PROTECTION	EACH	2
AR156540	RIPRAP	S.Y.	74
AR901510	SEEDING	ACRE	12
AR908510	MULCHING	ACRE	12

SEEDING DATA

THE GRADING LIMITS ARE SHOWN ON THIS SHEET BY A HEAVY DASHED LINE (---). ALL AREAS WITHIN THESE LIMITS, EXCEPT THE PROPOSED PAVEMENT, SHALL BE LIMED, FERTILIZED AND SEEDED IN ACCORDANCE WITH THE FOLLOWING FORMULA AND RATES OF APPLICATION.

LIME (TONS PER ACRE) _____ 2
 FERTILIZER (MINIMUM POUNDS OF AVAILABLE PLANT FOOD PER ACRE)

N	90
P ₂ O ₅	350
K ₂ O	240
TOTAL	680

SEEDING (MINIMUM POUNDS OF PURE LIVE SEED PER ACRE)

ALTA FESCUE	80
PERENNIAL RYEGRASS	30
CREeping RED FESCUE	20
SPRING OATS	48
AREA TO BE SEEDED	12 ACRES
DATE SEEDING COMPLETED	_____

MULCHING DATA

ALL EARTHEN AREAS WITHIN THE GRADING LIMITS WILL BE MULCHED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS AT THE RATE OF 2 TONS PER ACRE.


AREA TO BE MULCHED _____ 12 ACRES
 DATE MULCHING COMPLETED _____

NOTE

REFER TO THE CROSS-SECTIONS FOR GRADING AND SEEDING MATCH POINTS.

LEGEND

- EXISTING PAVEMENT
- PROPOSED IMPROVEMENTS
- PROPOSED GRADING AND SEEDING LIMITS
- PROPOSED INLET PROTECTION
- PROPOSED PIPE EXTENSION W/ HEADWALL
- DITCH CHECK



0' 25' 50' 100'
 FULL SIZE SCALE: 1" = 100'
 HALF SIZE SCALE: 1" = 200'

JUN 10, 2005 2:38 PM CCC
 I:\AIRPORTS\DECATUR\602-04TXWD\AIRPORT SHEETS\CONTRACT-2\F-181SWP.DWG - STA. 367+85.57 TO 403+57.30

DATE	REVISION	BY

IL PROJ.: DEC-3414 A.I.P. PROJ.: 3-17-0033-28

DECATUR, ILLINOIS

LAYOUT	W/M	04/15/05
DRAWN	DPE	04/15/05
REVIEWED	W/M	06/07/05

Engineers, Architects, Scientists
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

TAXIWAY G WIDENING
 PHASE II
 PROPOSED GRADING, SEEDING
 LIMITS, & EROSION CONTROL
 STA. 367+85.57 TO 403+57.30