



DATE	REVISION	BY
07/14/05	REVISED AS PER IDA REVIEW	CAH

FLORA AIRPORT  
FLORA, ILLINOIS

IL PROJ.: FOA-3506 A.L.P. PROJ.: 3-17-0044-911

DATE	REVISION	BY
04/27/05	RAW	CAH
04/27/05	RAW	CAH
04/27/05	REVIEWED	CAH

**HANSON**  
Hanson Professional Services Inc.  
1020 South Sixth Street  
Springfield, Illinois 62703-2888  
Chicago, Illinois

REMOVE AND REPLACE  
CLASS "E" FENCE

PROPOSED  
FENCING PLAN

**162-FENCING NOTES:**

THE PROPOSED FENCE WILL BE ERECTED ON THE SAME ALIGNMENT OF THE EXISTING 4'-FT CHAIN LINK FENCE (CLASS E), AS SHOWN. THE EXISTING FENCE FABRIC AND POSTS, INCLUDING ANY CONCRETE FOOTINGS AND OTHER ASSOCIATED ITEMS, WILL BE REMOVED PRIOR TO THE ERECTION OF THE PROPOSED CHAIN LINK (CLASS E) FENCE, AND PROPERLY DISPOSED OFF OF THE AIRPORT SITE AT THE EXPENSE OF THE CONTRACTOR. THE REMOVAL OF THE EXISTING FENCE WILL BE PAID FOR UNDER ITEM AR162900 - REMOVE CLASS E FENCE, PER L.F.

ALL FENCING PROPOSED WILL BE INSTALLED IN ACCORDANCE TO IDOT 664001-01 FOR CHAIN LINK FENCES, WITH THE EXCEPTION THAT A TOP RAIL WILL BE REQUIRED IN LIEU OF THE TOP TENSION WIRE, AND THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JULY 1, 2004. THE PROPOSED FENCE WILL BE PAID FOR UNDER ITEM AR162504 - CLASS E FENCE, 4', PER L.F.

THE CLASS E FENCE SHOWN WILL BE INSTALLED WITH THE FABRIC ON THE OUTSIDE OF THE FENCE POSTS. LIGHT CLEARING AND GRUBBING ON BOTH SIDES OF THE FENCE WILL BE REQUIRED TO ACCOMMODATE THE EQUIPMENT AND SPACE NECESSARY TO CONSTRUCT THE FENCE. ALL CLEARING AND GRUBBING NECESSARY TO COMPLETE THIS TASK WILL BE CONSIDERED INCIDENTAL TO THE ERECTION OF THE FENCE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

TEMPORARY REMOVAL OF THE MISCELLANEOUS DEBRIS (TRUCKS, TANKS, ETC.) NORTH OF THE EXISTING FENCE LINE AND PROPERTY OF THE ADJACENT REDI-MIX PLANT WILL BE THE RESPONSIBILITY OF THE PLANT OPERATOR. A PRIOR AGREEMENT WITH THE PLANT OPERATOR WILL BE MADE BY THE AIRPORT, HOWEVER THE CONTRACTOR WILL COORDINATE THE TEMPORARY REMOVAL OF THIS DEBRIS WITH THE PLANT OPERATOR PRIOR TO THE START OF THE PROJECT. THIS COORDINATION WILL BE CONSIDERED INCIDENTAL TO THE TASK OF CLEARING THE FENCE LINE FOR CONSTRUCTION OF THE PROPOSED FENCE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL CONCRETE UTILIZED TO CONSTRUCT THE FENCE WILL CONFORM TO ITEM 610 - STRUCTURAL PORTLAND CEMENT CONCRETE.

FENCING QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
AR162504	CLASS E FENCE, 4'	L.F.	1,195
AR162900	REMOVE CLASS E FENCE	L.F.	1,195

FENCE LOCATIONS			
POINT	NORTHING (Y)	EASTING (X)	DESCRIPTION
1	729,461.74	948,847.80	END POST
2	729,451.99	949,226.32	POINT ON LINE
3	729,445.88	949,519.67	END POST
4	729,441.15	949,716.73	END POST
5	729,443.60	949,984.07	POINT ON LINE
6	729,426.44	950,238.91	END POST

- EXISTING ROADWAY PAVEMENT
- EXISTING AIRFIELD PAVEMENT
- PROPOSED FENCE
- EXISTING FENCE
- EXISTING TREES AND LIGHT VEGETATION

