

SUMMARY OF QUANTITIES

PATH: K:\0051101\sheets\
 FILE: qty.dwg
 UPDATE BY: tmarin
 SURVEY BOOK #
 SURVEY DWG:
 XREF DWG:
 DATE: Tue 4/23/04 11:16am

ITEM NO.	DESCRIPTION	UNIT	TOTAL ESTIMATED QUANTITY	TOTAL RECORD QUANTITY	TAXIWAY G2 EXTENSION		NORTH QUADRANT SITEWORK - PHASE 1		ROADWAY INTERSECTION	
					FEDERAL/STATE/LOCAL	STATE/LOCAL	LOCAL ONLY	STATE/LOCAL	STATE/LOCAL	STATE/LOCAL
IDOT - STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS SPECIFIED ITEMS										
AR108030	1/2" #3/8 600 V UG CABLE	LF	750							
AR108158	1/2" #6 5 KV UG CABLE IN UD	LF	2550							
AR108408	1/2" #6 600 V UG CABLE	LF	2550							
AR108752	1/2" #2 GROUND	LF	75							
AR108780	1/2" #10 GROUND	LF	1050							
AR110212	2" STEEL DUCT, DIRECT BURY	LF	50							
AR110214	4" STEEL DUCT, DIRECT BURY	LF	180							
AR110217	1 1/2" STEEL DUCT, DIRECT BURY	LF	1050							
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	135							
AR110550	SPLIT DUCT	LF	260							
AR110810	ELECTRICAL HANDHOLE	EACH	3							
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	16							
AR125410	MIL - STAKE MOUNTED	EACH	31							
AR125415	MIL - STAKE MOUNTED	EACH	6							
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1							
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1							
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	2							
AR125470	MODIFY EXISTING SIGN PANEL	EACH	1							
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	4							
AR150510	ENGINEER'S FIELD OFFICE	LS	1							
AR150520	MOBILIZATION	LS	1							
AR152540	SOIL STABILIZATION FABRIC	SY	12620							
AR156510	SILT FENCE	LF	2250							
AR156511	DITCH CHECK	EACH	16							
AR156512	BALES	EACH	224							
AR156531	EROSION CONTROL BLANKET	SY	10250							
AR156540	RIPRAP	SY	30							
AR156543	RIPRAP - GRADATION NO. 3	SY	110							
AR156545	RIPRAP - GRADATION NO. 5	SY	250							
AR182506	CLASS E FENCE 8'	LF	400							
AR182612	CLASS E GATE - 12'	EACH	2							
AR182724	ELECTRICAL GATE 24'	EACH	1							
AR182960	RELOCATE CLASS E FENCE	LF	529							
AR201610	BITUMINOUS BASE COURSE	TON	1816							
AR208315	POROUS GRANULAR EMBANKMENT	CY	608							
AR208604	4" AGGREGATE BASE COURSE	SY	6140							
AR209607	CRUSHED AGG. BASE COURSE - 7"	SY	6140							
AR209608	CRUSHED AGG. BASE COURSE - 8"	SY	4280							
AR209611	CRUSHED AGGREGATE BASE COURSE - 11"	SY	2200							
AR401810	BITUMINOUS SURFACE COURSE	TON	1092							
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	71							
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	20							
AR510510	TIE DOWN	EACH	12							
AR510515	GROUND ROD	EACH	2							
AR602510	BITUMINOUS PRIME COAT	GAL	5955							
AR603510	BITUMINOUS TACK COAT	GAL	1773							
AR620520	PAVEMENT MARKING - WATERBORNE	SF	2770							
AR701006	6" PVC STORM SEWER	LF	190							
AR701184	PRECAST CONC. BOX CULVERT 8' X 4'	LF	216							
AR701512	12" RCP, CLASS IV	LF	65							
AR701515	15" RCP, CLASS IV	LF	465							
AR701518	18" RCP, CLASS IV	LF	675							
AR701524	24" RCP, CLASS IV	LF	116							
AR701900	REMOVE PIPE	LF	210							
AR705226	6" PERFORATED UNDERDRAIN W/SOCK	LF	1720							
AR705835	UNDERDRAIN COLLECTION STRUCTURE	EACH	2							
AR705900	REMOVE UNDERDRAIN	LF	760							
AR751411	INLET - TYPE A	EACH	2							
AR751410	MANHOLE 4'	EACH	5							
AR751900	REMOVE INLET	EACH	1							
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	1							
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH	1							
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	10							
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	2							
AR752512	GRATING FOR CONC. FES 12"	EACH	1							
AR752515	GRATING FOR CONC. FES 15"	EACH	1							
AR752518	GRATING FOR CONC. FES 18"	EACH	10							
AR752524	GRATING FOR CONC. FES 24"	EACH	2							
AR752900	REMOVE END SECTION	EACH	2							
AR754410	COMB. CONCRETE CURB & GUTTER	LF	1350							
AR754610	PAVED DITCH	LF	2600							
AR754915	REMOVE CONCRETE FLUME	LF	130							
AR780506	6" DUCTILE IRON WATER MAIN	LF	30							
AR780508	8" DUCTILE IRON WATER MAIN	LF	20							
AR780512	12" DUCTILE IRON WATER MAIN	LF	1750							
AR780800	FIRE HYDRANT	EACH	3							
AR780830	WATER VALVE	EACH	2							
AR780860	TAPPING VALVE & SLEEVE	EACH	1							
AR800001	TYPE 1 INLET	EACH	6							
AR800012	BOX CULVERT END SECTION 8' X 4'	EACH	6							
AR800020	BORING AND JACKING	LF	143							
AR800043	TYPE 2 INLET	EACH	1							
AR800048	DRAINAGE GATE 30"	EACH	1							
AR800088	5" STEEL DUCT, DIRECT BURY	LF	200							
AR800097	RESTRICTOR PLATE - TYPE A	EACH	3							
AR800098	RESTRICTOR PLATE - TYPE B	EACH	1							
AR800099	LINE STOP, B"	EACH	1							
AR800100	ELECTRIC SERVICE RELOCATION	LS	1							
AR800103	EMBANKMENT FILL	CY	22054							
AR800104	SHOULDER FILL	CY	3151							
AR800105	1/2" #4/0 600V UG CABLE	LF	120							
AR800106	STEEL PLATE BEAM GUARDRAIL - TYPE A	LF	280							
AR800107	STEEL PLATE BEAM GUARDRAIL - TYPE B	LF	65							
AR800110	ON-SITE STOCKPILE	CY	21729							
AR901511	SEEDING - FORMULA 1	ACRE	24.9							
AR901512	SEEDING - FORMULA 2	ACRE	0.7							

ITEM NO.	DESCRIPTION	UNIT	TOTAL ESTIMATED QUANTITY	TOTAL RECORD QUANTITY	TAXIWAY G2 EXTENSION		NORTH QUADRANT SITEWORK - PHASE 1		ROADWAY INTERSECTION	
					FEDERAL/STATE/LOCAL	STATE/LOCAL	LOCAL ONLY	STATE/LOCAL	STATE/LOCAL	STATE/LOCAL
IDOT - STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS SPECIFIED ITEMS										
AR904510	SODDING	SY	275							
AR905510	TOPSOILING (FROM ON SITE)	CY	8169							
AR905510	MULCHING	ACRE	22.8							
AR910101	ROADWAY LIGHT POLE, TYPE A	EACH	3							
AR910102	ROADWAY LIGHT POLE, TYPE B	EACH	2							
AR910161	ROADWAY LIGHTING TRANSCLOSURE	LS	1							
AR910200	ROADWAY SIGN	EACH	7							
AR910975	RELOCATE ROADWAY SIGN	EACH	1							
IDOT - STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION SPECIFIED ITEMS										
20200500	EARTH EXC WID	CY	140							
31101400	SUB GRAN MAT B 6	SY	100							
42000501	PCC PVT 10 JOINTED	SY	425							
44000100	PAVEMENT REM	SY	30							
44000500	COMB CURB GUTTER REM	LF	620							
44003100	MEDIAN REMOVAL	SF	3400							
44003800	MEDIAN SURF REMOVAL	SF	1600							
60250500	CB ADJ NEW TIF CL	EACH	2							
60608300	COMB CC&G TM2.12	LF	175							
60618200	BIT MEDIAN SURF	SF	1170							
60623714	CONC MEDIAN SPL	SF	830							
60623745	CONC MEDIAN TRANS	SF	360							
70102635	TR CONT & PROT 701701	LS	1							
72000100	SIGN PANEL T1	SF	9							
72000200	SIGN PANEL T2	SF	12							
72400800	REMOV SIGN COMPLETE	SF	18							
72400900	REMOV SIGN PANEL	EACH	1							
78001100	PT PVT MK LTRS & SYMB	SF	100							
78001130	PAINT PVT MK LINE 6"	LF	225							
78001180	PAINT PVT MK LINE 24"	LF	12							
78300100	PAVT MARKING REMOVAL	SF	100							
B1000300	CON T 1 GALVS	LF	65							
B1000600	CON T 2 GALVS	LF	220							
B1000700	CON T 2 1/2 GALVS	LF	200							
B1001000	CON T 4 GALVS	LF	20							
B1018500	CON P 2 GALVS	LF	47							
B1400100	HANDHOLE	EACH	1							
B1400200	HD HANDHOLE	EACH	2							
B5000200	MAIN EX TR SIG INSTAL	EACH	1							
B7301225	ELCBL C SIGNAL 14 3C	LF	250							
B7301245	ELCBL C SIGNAL 14 5C	LF	650							
B7301255	ELCBL C SIGNAL 14 7C	LF	650							
B7301305	ELCBL C LEAD 14 1PR	LF	1440							
B7702850	STL COMB MAA&P 24	EACH	1							