


SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	RECORD QUANTITY
AR108108	1/C #8 SKV UG CABLE	LF	8,840	
AR109210	VAULT MODIFICATIONS	LS	1	
AR109321	10 KW REGULATOR, STYLE 1	EACH	1	
AR110202	2" PVC DUCT, DIRECT BURY	LF	5,515	
AR110214	4" STEEL DUCT, DIRECT BURY	LF	160	
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	246	
AR110550	SPLIT DUCT	LF	375	
AR110610	ELECTRICAL HANDHOLE	EACH	2	
AR110714	ELECTRICAL MANHOLE 4"	EACH	7	
AR110907	REMOVE ELECTRICAL MANHOLE	EACH	1	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	12	
AR125415	MITL - BASE MOUNTED	EACH	59	
AR125441	TAXI GUIDANCE SIGN, 1 CHARACTER	EACH	2	
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	1	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	2	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	1	
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EACH	1	
AR125449	TAXI GUIDANCE SIGN, 9 CHARACTER	EACH	1	
AR125461	TAXI GUIDANCE SIGN, SPECIAL	EACH	1	
AR125470	MODIFY EXISTING SIGN PANEL	EACH	2	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	10	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	3	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR152540	SOIL STABILIZATION FABRIC	SY	19,960	
AR156510	SILT FENCE	LF	3,750	
AR156511	DITCH CHECK	EACH	7	
AR156520	INLET PROTECTION	EACH	16	
AR156540	RIP RAP	SY	50	
AR162960	RELOCATE CLASS E FENCE	LF	109	
AR163000	TEMPORARY CONSTRUCTION FENCE	LF	550	
AR201610	BITUMINOUS BASE COURSE	TON	190	
AR208515	POROUS GRANULAR EMBANKMENT	CY	1,800	
AR209606	CRUSHED AGG. BASE COURSE - 6"	SY	17,755	
AR209607	CRUSHED AGG. BASE COURSE - 7"	SY	1,625	
AR401610	BITUMINOUS SURFACE COURSE	TON	190	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	430	
AR501510	10" PCC PAVEMENT	SY	17,275	
AR501530	PCC TEST BATCH	EACH	1	
AR501900	REMOVE PCC PAVEMENT	SY	35	
AR602510	BITUMINOUS PRIME COAT	GAL	480	
AR603510	BITUMINOUS TACK COAT	GAL	120	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	9,875	
AR620525	PAVEMENT MARKING-BLACK BORDER	SF	11,850	
AR620900	PAVEMENT MARKING REMOVAL	SF	1,350	
AR701518	18" RCP, CLASS IV	LF	330	
AR701524	24" RCP, CLASS IV	LF	72	
AR701548	48" RCP, CLASS IV	LF	133	
AR701900	REMOVE PIPE	LF	250	
AR705526	6" PERFORATED UNDERDRAIN W/ SOCK	LF	4,100	
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	4	
AR705900	REMOVE UNDERDRAIN	LF	560	
AR705901	REMOVE UNDERDRAIN HEADWALL	EACH	1	
AR705905	REMOVE COLLECTION STRUCTURE	EACH	1	
AR751560	MANHOLE 6"	EACH	4	
AR751903	REMOVE MANHOLE	EACH	2	
AR751943	ADJUST MANHOLE	EACH	1	
AR751983	RECONSTRUCT MANHOLE	EACH	2	
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	1	
AR752518	GRATING FOR CONC. FES 18"	EACH	1	
AR752906	REMOVE INLET BOX	EACH	1	
AR800001	TYPE 1 INLET	EACH	1	
AR800028	SLOPE BOX INLET 18"	EACH	1	
AR800053	SOIL GUARD	SY	4,905	
AR800103	EMBANKMENT FILL	CY	14,000	
AR800104	SHOULDER FILL	CY	19,400	
AR901510	SEEDING	ACRE	13	
AR905510	TOPSOILING (FROM ON SITE)	CY	3,400	
AR908510	MULCHING	ACRE	12	

REVISIONS		
NUMBER	BY	DATE



**PALWAUKEE MUNICIPAL AIRPORT
 WHEELING/PROSPECT HEIGHTS, ILLINOIS**

CONSTRUCT TAXIWAY CHARLIE AND EAST QUADRANT APRON

SUMMARY OF QUANTITIES

© Copyright CMT, Inc.

CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 184-000513

DESIGN BY:	MJK
DRAWN BY:	JRO
CHECKED BY:	
APPROVED BY:	
DATE:	06/24/05
JOB No:	04290-03
ILLINOIS PROJECT: PWK-3481 A.I.P. PROJECT: 3-17-0018-BXX	
SHEET 2 OF 38 SHEETS	